

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

15-129-6140-0000

APR 27 1964  
4-27-64  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Pan American Petroleum Corp.

Complete Address: Box 432 Liberal, Kansas

Lease Name Winter Gas Unit "C" Well No. # 1

Location C SW NE Sec. 27 Twp. 31 Rge. (E) (W) 40

County Morton Total Depth 6050'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Knight Casing Pulling Co.

Address: Chase, Kansas License No. 436

Operation Completed: Hour 3 PM Day 24 Month 4 Year 64

The Above well was plugged as follows:

8 5/8"-698' Cir. w/cement. 5 1/2"-6050' Cemented. Perforations 5526' to 5530'

Plug bottom w/10 Sax. cement top cement 5420' Mud 5420' to 600'

35 Sax. cement 600' to 500' Mud 500' to 55'

Rock bridge 55' to 45' 15 Sax. cement 45' to 0

Pulled 2716' 5 1/2" pipe. Company Pump. Cut pipe off 4' below ground level.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 4/28/64

INV. NO. 9048-w