



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
APR 5 - 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name McBride Operating Company - 15-175-2046-0006

Complete Address 215 Avondale, Wichita Falls, Texas 76308

Lease Name Lambert Well No. 1

Location App C SW Sec. 32 Twp. 31 Rge. 32 (E) (W)

County Seward Total Depth 2731'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 405, Chase, Kansas License No. 624

Operation Completed: Hour 4:00Pm Day 29 Month 3 Year 1974

The above well was plugged as follows:

- 8 5/8" to 661' circulated w/ cement. 4 1/2" to 2730' cemented.
- Top perforations 2664' Plug bottom w/ 20 sacks cement.
- Top of cement 2500' Mud 2500' to 600'
- Spotted 35 sacks cement 600' to 500' Mud 500' to 45'
- Plug, Halls " 15 sacks cement 45' to 0'. Halliburton Pump
- Pulled 1094' of 4 1/2" casing.

INVOICED

I hereby certify that the above well was plugged as herein stated

DATE 4/5/74
INV. NO. 8892-W

Signed: [Signature]
Well Plugging Supervisor