

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

FORM CP-3
1-8-82
RECEIVED
STATE CORPORATION COMMISSION
JUL 28 1982
CONSERVATION DIVISION
Wichita, Kansas

API Number 15-175-

00544-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Amoco Production Co

Complete Address Box 432, Liberal Kansas 67901

Lease Name Seroy Lambert Well No. 1

Location C-NW-5W Sec. 35 Twp. 31 Rge. 33 (East) (West)

County Seward Total Depth 6000'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Midwest Casing Pulling

Address Box F Sublett Kans 67877 License No. 766

Operation Completed: Hour: 4:00 PM. Day: 19 Month: 7 Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

They cement circulated 750' of 8 5/8" surface casing. The set 6000' of 5 1/2" production pipe with plug back at 4946'. The perforated pipe from 4934' to 38'. They set cast iron plug above perforations & put 1 bbl of cement on it. 2nd plug pumped 50 bbl of cement on top of stub. 3rd plug pumped 35 bbl of cement through 5 1/2" to 500'. 4th plug an solid bridge at 40' to 0' with 10 bbl of cement. They recovered 1212' of 5 1/2" production pipe. The plugging was accomplished by Midwest casing pulling.

Amount of Surface Casing: 750' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthi
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

I was on a well in my area.

Signed: Paul A. Luthi
Conservation Division Agent

INVOICED
DATE 7-28-82
INVOICE NO. 7-57-N