

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15- 134 15-175-00511-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Heimerich & Payne Inc.

Complete Address Box 558, Garden City Kans 67846

Lease Name Hyde Well No. 1

Location C-5W Sec. 14 Twp. 31 Rge. 34 (East)(West)

County Seward Total Depth 2850'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Post & Martin Well service Inc.

Address Garden City, Kansas 67846 License No. _____

Operation Completed: Hour: 6:30 PM Day: 30 Month: 8 Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

They set 5 1/2" production pipe set at 2610'. They sanded back to 2540' & pumped 15 skb of cement on top of sand. 2nd plug at 1150' to 1400' with 35 skb of cement. 3rd plug at 625' with 15 skb of cement. 4th plug was at 60' to 0' with 10 skb of cement. Then they tied on to the surface & pumped 20 skb of cement. The cement pumped was class H. The plugging was accomplished by Dowell Cementing. There was no pipe scoured. The cement was pumped through tubing.
Amount of Surface Casing: 10 3/4" at 56.3'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthi
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

I was on another well at this time.

INVOICED Signed: Paul A. Luthi
Conservation Division Agent

DATE 9-9-82

INV. NO. 1073-W

Sept. 2 '82