

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-25446-00-00  
Spot: SENWNWNW Sec/Twnshp/Rge: 28-17S-15W  
380 feet from N Section Line, 640 feet from W Section Line  
Lease Name: GERARD AXMAN Well #: 1  
County: BARTON Total Vertical Depth: 3651 feet

Operator License No.: 5259  
Op Name: MAI OIL OPERATIONS, INC.  
Address: 8411 PRESTON RD STE 800  
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3646	2440	160 SX
SURF	8.625	1071		350 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/06/2015 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: ALLEN BANGERT Company: MAI OIL OPERATIONS Phone: (214) 219-8883

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/06/2015 12:00 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped off with cement. Cut casing at 2440'. Pulled casing to 1500' and pumped 125 sx cement w/200 # hulls. Pulled casing to 900' and pumped 50 sx cement w/100 # hulls. Pulled casing to 600' and pumped 50 sx cement w/100 # hulls. Pulled casing to 300'. Circulated cement to surface with 100 sx cement. Pulled casing. Hole stayed full.

GPS: 38.55009 -098.99430

Perfs:

Top	Bot	Thru	Comments
3596	3602		
3502	3506		
3423	3427		


Remarks: QUALITY OILWELL CEMENTING

Plugged through: CSG

4/22/15 CKM

District: 04

Signed



Received (TECHNICIAN)  
KANSAS CORPORATION COMMISSION

CM

APR 16 2015

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3

APR 08 2015