

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-077-21333-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 9-31S-9W
2310 feet from S Section Line, 330 feet from W Section Line
Lease Name: COX "B" Well #: 1-9
County: HARPER Total Vertical Depth: 4528 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 9342 E CENTRAL
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4525	1860	100 SX
SURF	8.625	215		165 SX

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 08/20/2014 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD Company: QUALITY WELL SERVICE Phone: _____

Proposed Plugging Method: SAND TO 4400 & 5 SXS CEMENT. RECOVER PIPE. 35 SX 1400', 35 SX 900'. CIRCULATE 265'-0'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 04/16/2015 6:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

PUMPED 200# HULLS & 30 SX CEMENT TO 4385' SI. 800#. REC 1860' OF CASING.
PULLED CASING TO 1400' SPOTTED 35 SXS CEMENT. PULLED CASING TO 900',
SPOTTED 35 SXS CEMENT. PULLED CASING TO 265' & CIRCULATED CEMENT TO
0'.

Perfs:

Top	Bot	Thru	Comments
4444	4453	CSG	

Remarks: QUALITY WELL SERVICE COMMON CEMENT

Plugged through: CSG

District: 02

Signed _____

[Signature] 5/22/14 *[Initials]*

KCC WICHITA (TECHNICIAN)

APR 22 2015

RECEIVED