

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-24210-00-02
Spot: W2W2SW Sec/Twnshp/Rge: 19-18S-11W
1320 feet from S Section Line, 4950 feet from E Section Line
Lease Name: SCHREPEL Well #: 4
County: BARTON Total Vertical Depth: 3625 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3621		175 SX
SURF	8.625	652		250 SX

Well Type: WSW UIC Docket No: _____ Date/Time to Plug: 03/20/2015 9:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Revd. from: STAN FROETSCHNER Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/20/2015 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1400' and 640'. Ran tubing to 2700' and pumped 140 sx cement. Pulled tubing to 1500' and pumped 125 sx cement w/150 # hulls. Pulled tubing to 650' and pumped 75 sx cement. Circulated cement on casing. Shut valve on casing and circulated cement to surface on surface pipe with 125 sx cement. Pulled tubing and topped off with 5 sx cement.

GPS: 38.46744 -098.58989

Perfs:

Top	Bot	Thru	Comments
3520	3530		
3508	3512		
3486	3496		
3448	3456		
3432	3438		
3182	3190		
2918	2922		
2746	2749		

Remarks: QUALITY OILWELL CEMENTING

Plugged through: CSG

4/22/15 ckm

District: 04

Signed Bruce Rodie

Received (TECHNICIAN)
KANSAS CORPORATION COMMISSION

ckm

MAR 30 2015

APR 16 2015

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS