

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-179-21353-00-00  
Spot: SESWNESE Sec/Twnshp/Rge: 14-7S-30W  
1440 feet from S Section Line, 930 feet from E Section Line  
Lease Name: STEVENSON Well #: 1-14  
County: SHERIDAN Total Vertical Depth: 4589 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4580		175 SX
SURF	8.625	301		375 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/07/2015 8:30 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN GERSTMER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 12 sx gel (1200#) and 500 # hulls.  
8 5/8" surface casing set at 301' w/375 sx cement. 5 1/2" production casing set at 4580' w/175 sx cement. Port collar set at 2572' w/175 sx cement. TD 4589', PBTD 4467'. Perforations: 4361' - 4368', 3974' - 3980', 3960' - 3964' and 3940' - 3944'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/07/2015 11:30 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 4213' and pumped 12 sx gel followed by 100 sx cement w/400 # hulls. Pulled tubing to 2576' and pumped 125 sx cement. Pulled tubing to 1269' and pumped 140 sx cement. Cement to surface. Pulled tubing to surface. Connected to 5 1/2" production casing and pumped 17 sx cement. Connected to 8 5/8" surface casing and pumped 10 sx cement. Pressured to 300 psi.

GPS: 39.44133N -100.63034W

Perfs:

Top	Bot	Thru	Comments
4361	4368		
3974	3980		
3960	3964		
3940	3944		

Remarks:

Plugged through:

4/22/15 ckm

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

CM

Received  
KANSAS CORPORATION COMMISSION

APR 20 2015

CONSERVATION DIVISION  
WICHITA, KS

APR 14 2015

Form CP-2/3