

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-185-02010-00-00  
Spot: SWSWSE Sec/Twnshp/Rge: 12-22S-13W  
332 feet from S Section Line, 2306 feet from E Section Line  
Lease Name: SCHEIB Well #: 1  
County: STAFFORD Total Vertical Depth: 3683 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	6	800		
PROD	6	3674	0	WITH 100 SX CMT
SURF	10.75	255		WITH 270 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/07/2015 10:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: MARK ROBBEN Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: PUMP 75 SX CMT ON BOTTOM WITH TBG. PULL TO 790' & CIRCULATE CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/07/2015 4:14 PM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

SET RBP @ 800'. RAN CBL, HAD GOOD BOND TO SURFACE. SQUEEZE BOTTOM PERF @ 3650' WITH 120# HULLS & 75 SX CMT THROUGH TBG. PULLED TBG OUT TO 800'. PUMP THROUGH TBG AT 800' WITH 160# HULLS & 220 SX CMT. DID NOT CIRCULATE. WAIT 2 HOURS. RAN WIRELINE TO 1100' & DID NOT TAG TOC. SET 6" CIBP @ 800'. PUMPED THROUGH TBG WITH 180 SX CMT. CMT DID CIRCULATE TO SURFACE. TOPPED OFF WELL HEAD WITH CMT.

Perfs:

Top	Bot	Thru	Comments
3674	3682		

Remarks: USED 60/40 POZMIX 4% GEL BY HURRICANE SERVICES.

Plugged through: CSG

4/22/15 OKM

District: 01

Signed Robert Dickerson

(TECHNICIAN)

RECEIVED  
APR 15 2015  
KCC DODGE CITY

SA

Received  
KANSAS CORPORATION COMMISSION

Form CP-2/3

APR 20 2015

CONSERVATION DIVISION  
WICHITA, KS