

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-21087-00-00
Spot: NESESWSE Sec/Twnshp/Rge: 12-22S-13W
469 feet from S Section Line, 1494 feet from E Section Line
Lease Name: SCHEIB Well #: 4
County: STAFFORD Total Vertical Depth: 3693 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3674	0	WITH 125 SX CMT
SURF	8.625	732		WITH 500 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/02/2015 9:20 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: MARK ROBBIN Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: SQUEEZE BOTTOM PERF WITH 100# HULLS & 75 SX CMT. PERFORATE @ 760' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/02/2015 11:30 AM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

TBG STACKED OUT AT 2828'. PUMP THROUGH TBG AT 2828' WITH 150# HULLS & 75 SX CMT. TAG TOC @ 2600'. PERFORATE AT 760' & PUMP DOWN 5 1/2" CASING WITH 225 SX CMT. CMT CIRCULATED TO SURFACE. TOPPED OFF WELL HEAD WITH CMT.

Perfs:

Top	Bot	Thru	Comments
3674	3693		
3466	3472		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: CSG

4/22/15 *cm*

District: 01

Signed Robert Dickerson
(TECHNICIAN)

RECEIVED
APR - 8 2015
KCC DODGE CITY

MP

SA

Received
KANSAS CORPORATION COMMISSION Form CP-2/3
APR 20 2015
CONSERVATION DIVISION
WICHITA, KS