

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-23179-00-00
Spot: SESESWSW Sec/Twnshp/Rge: 8-22S-12W
100 feet from S Section Line, 4080 feet from E Section Line
Lease Name: TEICHMAN UNIT Well #: 1-8
County: STAFFORD Total Vertical Depth: 3819 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3371		WITH 2 SX CMT
CIBP		3728		
PROD	5.5	3816	0	WITH 125 SX CMT
SURF	8.625	699		WITH 390 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/01/2015 9:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: MARK ROBBIN Company: MURFIN DRILLING CO., INC. Phone: (316)267-3241

Proposed
Plugging
Method:

SET CIBP 50' ABOVE TOP PERF. BOND LOG, PERFORATE & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/01/2015 12:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PERFORATED AT 806' & SQUEEZED WITH 100 SX CMT AT AN EARLIER DATE.
SET CIBP @ 3371' & PUT 2 SX CMT ON TOP OF CMT THROUGH DUMP BAILER.
BOND LOG. FOUND EXCELLENT CMT BOND FROM 720'-1010'. PERFORATE 5 1/2"
CASING AT 680'. PUMP DOWN 5 1/2" CASING WITH 140 SX CMT. CMT
CIRCULATED UP 5 1/2" X 8 5/8" ANNULUS LEAVING CMT TO SURFACE IN 5 1/2"
CASING & 5 1/2" X 8 5/8" ANNULUS.

Perfs:

Top	Bot	Thru	Comments
3744	3747		
3731	3735		
3728	3728		CIBP
3694	3700		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: CSG

District: 01

Signed

Steve Pfeifer
(TECHNICIAN)

5A

4/22/15 CRM

RECEIVED
APR - 8 2015
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION
Form CP-2/3
APR 20 2015
CONSERVATION DIVISION