

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-23945-00-00
Spot: N2N2SW Sec/Twnshp/Rge: 23-33S-12W
2275 feet from S Section Line, 1292 feet from W Section Line
Lease Name: COLBORN A Well #: 1
County: BARBER Total Vertical Depth: 4941 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 124 N MAIN PO BOX 195
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4569		
PROD	5.5	4921	3115	WITH 125 SX CMT
SURF	8.625	263		WITH 225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/07/2015 2:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 30 SX CMT & 200# HULLS TO 4490'. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 280' WITH 40 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/07/2015 3:40 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PUMPED DOWN 5 1/2" CASING WITH 200# HULLS & 30 SX CMT. SHUT IN PRESSURE AT 1200#. TAGGED TOC @ 4490'. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 280' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4550	4556		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

4/22/15 CKM

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
APR 16 2015
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION CP-2/3

APR 20 2015 4-20-2015

CONSERVATION DIVISION
WICHITA, KS