

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-24846-00-00
Spot: NESWSW Sec/Twnshp/Rge: 10-16S-11W
1160 feet from S Section Line, 1070 feet from W Section Line
Lease Name: REDETZKE FARMS Well #: 1-10
County: BARTON Total Vertical Depth: 3419 feet

Operator License No.: <u>3882</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>SAMUEL GARY JR. & ASSOCIATES, IN</u>	<u>PROD</u>	<u>5.5</u>	<u>3414</u>		<u>225 SX</u>
Address: <u>1515 WYNKOOP, STE 700</u>	<u>SURF</u>	<u>8.625</u>	<u>455</u>		<u>275 SX</u>
<u>DENVER, CO 80202</u>	<u>T1</u>	<u>2.375</u>	<u>3357</u>		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/02/2015 8:00 AM
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.
Proposal Rcvd. from: LEE BIEBERLE Company: SAMUEL GARY Phone: (620) 786-4601

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 400 # hulls and 13 sx gel.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/02/2015 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1500', 700' and 440'. Ran tubing to 3320' and pumped 13 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1500' and pumped 80 sx cement w/200 # hulls. Pulled tubing to 700'. Circulated cement to surface with 180 sx cement on casing and surface pipe. Pulled tubing and topped off with 20 sx cement.

GPS: 38.67032 -098.53130

Perfs:

Top	Bot	Thru	Comments
3204	3206		
3197	3199		
3192	3194		
3054	3058		

Remarks: QUALITY OILWELL CEMENTING

Plugged through: TBG

4/22/15 *um*

District: 04

Signed *Bruce Rodie*

Received (TECHNICIAN)
KANSAS CORPORATION COMMISSION

CM

APR 08 2015

APR 16 2015

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS