

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-179-21393-00-00  
Spot: E2W2SWSW Sec/Twnshp/Rge: 21-10S-30W  
660 feet from S Section Line, 500 feet from W Section Line  
Lease Name: SCHWARZ Well #: 1-21  
County: SHERIDAN Total Vertical Depth: 4623 feet

Operator License No.: 3882  
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN  
Address: 1515 WYNKOOP, STE 700  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	263		200 SX

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/04/2015 12:00 AM  
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING  
Proposal Rcvd. from: TOM Company: DISCOVERY DRILLING Phone: (620) 793-2920

Proposed Plugging Method: Ordered 255 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: MARVIN MILLS Witness Type: NONE  
Date/Time Plugging Completed: 03/04/2015 4:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

1st plug @2530 w/50 sx 2nd plug @975 w/100 sx 3rd plug @315 w/50 sx 4th plug @40 w/10 sx  Rathole 30 sx Mousehole 15 sx
--

Perfs:

Received  
KANSAS CORPORATION COMMISSION  
**APR 16 2015**  
CONSERVATION DIVISION  
WICHITA, KS

4/22/15ckm

Remarks: QUALITY  
Plugged through: DP

District: 04 Signed [Signature] (TECHNICIAN) CM