

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-20267-00-00
Spot: NESENE Sec/Twnshp/Rge: 2-17S-29W
3630 feet from S Section Line, 330 feet from E Section Line
Lease Name: GILL A Well #: 3
County: LANE Total Vertical Depth: 4578 feet

Operator License No.: 30029
Op Name: STANDARD OPERATING COMPANY
Address: 1000 N TYLER STE 100
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT	5.5	2180		WITH 500 SX CMT
PROD	5.5	4592	0	WITH 200 SX CMT
SURF	8.625	626		WITH 170 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/13/2015 1:00 PM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: DAVID PAULEY Company: STANDARD OPERATING Phone: (785) 798-5051

Proposed Plugging Method: SAND 50' ABOVE PERFS & 5 SX CMT. RUN TBG TO 2200' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. USE 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/13/2015 2:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SANDED BOTTOM TO 4100' WITH 5 SX CMT. RUN TBG TO 2200' & PUMPED 330 SX CMT. DID NOT CIRCULATE. PULLED TBG & WILL TOP OFF LATER. TIED ONTO BACKSIDE & PUMPED 20 SX CMT. PRESSURED TO 300# & HELD. 3/20/15: TOPPED OFF CASING WITH 100 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4525	4528		
4518	4522		
4497	4500		
4491	4495		
4372	4375		
4361	4365		
4310	4316		
4125	4130		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

4/22/15 CKM

District: 01

Signed Michael Maier
SA (TECHNICIAN)

RECEIVED
APR - 8 2015
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION Form CP-2/3
APR 20 2015
CONSERVATION DIVISION
WICHITA, KS