

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-035-20613-00-00  
Spot: NENWSW Sec/Twnshp/Rge: 36-31S-4E  
2326 feet from S Section Line, 4337 feet from E Section Line  
Lease Name: HOLT Well #: 5  
County: COWLEY Total Vertical Depth: 3009 feet

Operator License No.: 34886  
Op Name: TOTO ENERGY, LLC  
Address: 25815 OAK RIDGE DR  
SPRING, TX 77380

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3004	250	250 SX
SURF	8.625	200		150 SS CMT
SURF	8.625	205		140 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/18/2015 8:00 AM  
Plug Co. License No.: 34879 Plug Co. Name: CANAAN WELL SERVICE INC.  
Proposal Rcvd. from: TERRY MADDEN Company: TOTO ENERGY, LLC. Phone: (620) 804-2202

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL  
Date/Time Plugging Completed: 12/23/2014 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE, SET CIBP @ 2915', DUMP BAILED 4 SXS OF CEMENT ON TOP OF PLUG. CUT CASING @ 650', & 250', LAYED DOWN 9 JOINTS 5 1/2" CASING (250'). RIH W/ TBG @ 270', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 75 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. CEMENT CIRCUALTED. PLUG DOWN 11:30 AM 12-23-2014. CONSOLIDATED CEMENT TICKET #48540.

Perfs:

Top	Bot	Thru	Comments
2986	2990		CSG

Remarks: PARTS OF 5 1/2" ANCHOR & 2 JOINTS 2 7/8" TBG @ 2922'.

Plugged through: TBG

4/22/15 CKM

District: 02

Signed

DUANE KRUEGER

(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

APR 20 2015

Form CP-2/3

CONSERVATION DIVISION  
WICHITA, KS

JK