

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-035-30015-00-02  
Spot: NWSWNE Sec/Twnshp/Rge: 36-31S-4E  
3718 feet from S Section Line, 2403 feet from E Section Line  
Lease Name: HOLT B Well #: 1  
County: COWLEY Total Vertical Depth: 3050 feet

Operator License No.: 34886  
Op Name: TOTO ENERGY, LLC  
Address: 25815 OAK RIDGE DR  
SPRING, TX 77380

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	0	0		0 SX
PROD	5.5	2370		
SURF	8.625	214		125 SX

Well Type: SWD UIC Docket No: D22135.0 Date/Time to Plug: 12/23/2015 8:00 AM  
Plug Co. License No.: 34879 Plug Co. Name: CANAAN WELL SERVICE INC.  
Proposal Rcvd. from: TERRY MADDEN Company: TOTO ENERGY, LLC Phone: (620) 804-2202

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL  
Date/Time Plugging Completed: 12/24/2014 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE, SET CIBP @ 1890', DUMP BAILED 4 SXS OF CEMENT ON TOP OF PLUG. PRESSURED CASING, HELD OK. RIH ON WIRELINE SHOT SQUEEZE HOLES 270'-271' (4 HOLES). SWEDGED INTO 5 1/2" CASING, CONSOLIDATED OILWELL SEVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 110 SXS 60/40 POZMIX 4% GEL 2% CC. CEMENT DID NOT CIRCUALTE 12/24/2014 TAGGED CEMENT @ 375'. RIH W/ 1" TUBING ON BACKSIDE @ 110', CONSOLIDATED MIXED & PUMPED 15 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED DOWN 1" TBG. RIH W/TBG @ 260', CONSOLIDATED ESTABLISHED. MIXED & PUMPED 95 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. CEMENT CIRCUALTED. CONSOLIDATED CEMENT TICKET #48541.

Perfs:

Top	Bot	Thru	Comments
1940	1970		CSG

Remarks: COMPLIANCE/ FAILED MIT

Plugged through: TBG

District: 02

Signed DUANE KRUEGER  
(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

APR 20 2015

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3

CC: UIC