

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-101-20321-00-01  
Spot: SWNENW Sec/Twnshp/Rge: 10-17S-29W  
4271 feet from S Section Line, 3617 feet from E Section Line  
Lease Name: THON Well #: 1  
County: LANE Total Vertical Depth: 4610 feet

Operator License No.: 4313  
Op Name: WALKER TANK SERVICE, INC  
Address: 478 S OHIO PO BOX 117  
UTICA, KS 67584

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2181		
PROD	4.5	4598	0	WITH 450 SX CMT
SURF	8.58	285		WITH 200 SX CMT

Well Type: SWD UIC Docket No: D24051.0 Date/Time to Plug: 03/18/2015 1:00 PM  
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
Proposal Rcvd. from: GALEN WALKER Company: QUALITY OIL WELL CEMENTING Phone: (785) 391-1035

Proposed Plugging Method: RUN TBG TO BOTTOM & CIRULATE CMT TO SURFACE. PULL TBG & TOP OFF. IF POSSIBLE, TIE ONTO BACKSIDE & PUMP 50 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/18/2015 3:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

**\*\*CASING WAS PERFORATED AND 450 SX CMT WAS USED TO CIRCULATE CMT TO SURFACE WHEN WELL WAS COMPLETED FOR A DISPOSAL WELL.\*\* RUN TBG TO 1507' & PUMP 100 SX CMT & 250# HULLS. CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 15 SX CMT. DIDN'T TIE ONTO BACKSIDE IT WAS FULL OF CMT.**

Perfs:

Top	Bot	Thru	Comments
1860	1960		

Remarks: USED 60/40 POZMIX 4% GEL BY QULAITY WELL SERVICE.

Plugged through: TBG

*4/22/15 ccm*

District: 01

Signed *Michael Maier*  
5A (TECHNICIAN)

RECEIVED  
APR - 8 2015  
KCC DODGE CITY *MP*

Received  
KANSAS CORPORATION COMMISSION Form CP-2/3

APR 20 2015  
CONSERVATION DIVISION  
WICHITA, KS

*CC:uic*