

1060294

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 025-20,814 - 00-00

NW NW NW, SEC. 33, T 31 S, R 24 W/E
4950 ^{FSV} feet from N SE Corner of NXX section line
4950 ^{FEV} feet from W SE Corner of NXX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7381

Lease Name Glenda Morton Well # 1

Operator: Mitchell Energy Corporation

County Clark

Name & Address P. O. Box 4000

Well Total Depth 7050 ^{229.13} feet

The Woodlands, TX 77380

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 645

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Eagle Drilling, Inc. License Number 5380

Address P. O. Box 8609, Wichita, KS 67208

Company to plug at: Hour: 4:00 pm Day: 3 Month: August Year: 19 84

Plugging proposal received from Butch Steinert

(company name) Eagle (phone) 316-682-5513

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 1500' with 50 sx cement

2nd plug at 720' with 50 sx cement

3rd plug at 400' with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement.

6th plug to circulate rat hole with 10 sx cement, 7th plug to circulate mouse hole with 10 sx cement. Plugging Proposal Received by Paul A. Luthie
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 6:45 pm Day: 3 Month: August Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1500' with 50 sx cement, 2nd plug at 720' with 50 sx

cement, 3rd plug at 400' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug

at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 10

sx cement, 7th plug to circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton

(If additional description is necessary, use BACK of this form.)

(operator / technician) observe this plugging.

INVOICED

DATE 8-16-84

Signed Paul A. Luthie
(TECHNICIAN)

INV. NO. 3216

8-3

RECEIVED
STATE CORPORATION COMMISSION

AUG 07 1984

CONSERVATION DIVISION
Wichita, Kansas