

1 060933

JAN 30 1987

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 025-20,969 4000

C NW SW, SEC. 32, T 31 S, R 22 W/E
1980 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5359

Lease Name Comstock Well # 1-32

Operator: Bogert Oil Company
Name & Address 2601 N.W. Expressway #1000-W
Oklahoma City, OK 73112

County Clark 227.50

Well Total Depth 7000 feet

Conductor Pipe: Size 16" feet 59

Surface Casing: Size 8 5/8" feet 766

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company License Number 6033

Address 250 North Water, Wichita, KS 67202

Company to plug at: Hour: 8:45 p.m. Day: 29 Month: 1 Year: 19 87

Plugging proposal received from Ernie Brimb

(company name) Bogert Oil Company (phone) 405-848-5808

were: to fill hole with heavy mud and spot cement through drill pipe. Elevation 2150' Anhydrite 2000'

1st plug at Arbuckle with 25 sx cement, 2nd plug at Base Anhydrite with 50 sx cement,

3rd plug at 30' out base of surface pipe with 50 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 5 a.m. Day: 30 Month: 1 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 6900' with 25 sx cement,

2nd plug at 1020' with 50 sx cement,

3rd plug at 790' with 50 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used Class H 1/2% FR 2 cement by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-3-87 FEB 2 2-3-87

Signed Paul A. Luthi
(TECHNICIAN)

INV. NO. 16065

FORM CP-2/3
Rev. 01-84To
DEEP
FOR
STONE
CORREL

NOTICE OF INTENTION TO DRILL

Dec. 2 1986

(see rules on reverse side)

Starting Date month day year

API Number 15- 015-20,969-0000

OPERATOR: License # 5359
 Name Bogert Oil Company
 Address 2601 N.W. Expressway #1000-W
 City/State/Zip Oklahoma City, OK 73112
 Contact Person Gerald Smith
 Phone 405 848 5808

C'NW SW Sec. 32 Twp. 31 S, Rg. 22 X West
 1980 Ft. from South Line of Section
 4620 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 660 feet
 County Clark

CONTRACTOR: License # 6033
 Name Murfin Drilling Co.
 City/State 250 N. Water, Wichita, KS 67202

Lease Name Comstock Well # 1-32

Ground surface elevation (2150) feet MSL

Well Drilled For: Well Class: Type Equipment:
 X Oil SWD Infield X Mud Rotary
 X Gas Inj Pool Ext. Air Rotary
 OWWO Expl X Wildcat Cable

Domestic well within 330 feet: yes X no

Municipal well within one mile: yes X no

Depth to bottom of fresh water 120

Depth to bottom of usable water 200

Surface pipe by Alternate: 1 X 2

Surface pipe planned to be set 800

Conductor pipe required 40-45ft

Projected Total Depth 7135 feet

Formation Arbuckle

If OWWO: old well info as follows:

Operator

Well Name

Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 11/18/86 Signature of Operator or Agent *Calvin Dickman* Title AS agent

For KCC Use:

Conductor Pipe Required 5-18-87 feet; Minimum Surface Pipe Required 225 feet per Ali D

This Authorization Expires 5-18-87 Approved By 11-18-86

*Spud 12-27-86 set 800' at 8:00
 Move in 1-14-87 set 800' at 8:00 & 59' at 16:11*

C'NW SW Sec. 32 Twp. 31 S, Rg. 22 X West

Set 750 + -

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Plug #	Depth (ft)	Material	Notes
1st plug @	TD	50-25	sxs of cement
2nd plug @	3100	50	sxs of cement
3rd plug @	1600	50	sxs of cement
4th plug @	700	50	sxs of cement
5th plug @	350	10	sxs of cement

(2) Rathole with 10-15 sxs Mousehole with sxs

PUSHER *Conney Burdick*
 TD 700 FORMATION Arbuckle
 SURFACE PIPE 8 3/8 @ 766 16'25"
 ANHYDRITE 2000 ELEVATION 2150
 STARTING TIME & DATE 1-29-86 8:45 PM
 COMPLETION TIME & DATE 1-30-86 5:00 PM
 Tap 6898
 1st PLUG @ 6800 FT. W/ 2.5 SX
 2nd PLUG @ 1020 FT. W/ 50 SX
 3rd PLUG @ 790 FT. W/ 50 SX
 4th PLUG @ 40-0 FT. W/ 10 SX
 RAT HOLE CIRCULATED W/ 15 SX
 MOUSE HOLE CIRCULATED W/ SX
 WATER WELL PLUGGED W/ None SX
 CEMENT COMPANY Halliburton
 TECHNICIAN *Paul Smith*
 60540000
 Closed 4 1/2 FR2

RECEIVED
 CORPORATION COMMISSION

FEB 4 1987

CONSERVATION DIVISION
 Wichita, Kansas