

1 060887

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-025-20,963-0600

app. SW NW SW. SEC. 34, T 31 S, R 22 W/4

1620 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5359

Lease Name Waits Well # 2-34

Operator: Bogert Oil Company

County Clark 216.13

Name & Address 2601 N.W. Expressway #1000-W

Well Total Depth 6650 feet

Oklahoma City, OK 73112

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 807

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Co. License Number 6033

Address 250 N. Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 4 a.m. Day: 22 Month: 10 Year: 19 86

Plugging proposal received from Marvin Julian

(company name) Murfin Drilling Co. (phone) 316-234-5665

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2140' Anhydrite 1400'

1st plug at Top of the Arbuckle with 50 sx cement

2nd plug at set base of base Anhydrite with 40 sx cement

3rd plug at 730' with 40 sx cement

4th plug at 0-40' with 10 sx cement, 5th plug to circulate rathole with 15 sx cement

Plugging Proposal Received by Don Ubel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:15 a.m. Day: 22 Month: 10 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 6650' with 50 sx cement

2nd plug at 1400' with 40 sx cement

3rd plug at 780' with 40 sx cement

4th plug at 40-0' with 10 sx cement

5th plug to circulate rathole with 15 sx cement 10-24-86

RECEIVED
STATE CORPORATION COMMISSION
CONS. DIV. WICHITA, KS

OCT 24 1986

Remarks: Used Class H cement by Halliburton.
(if additional description is necessary, use BACK of this form.)

INVOICED

Observe this plugging.

DATE 10-24-86

Signed Paul A. Luthi (TECHNICIAN)

INV. NO. 15235

10-22

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 10/1/86 month day year

API Number 15- 025-20,963,0000

OPERATOR: License # 5359

app. SW. NW SW 34 Twp. 31 S. Rg. 22 West

Name Bogert Oil Company

1620 Ft. from South Line of Section

Address 2601 N.W. Expressway #1000-W

4950 Ft. from East Line of Section

City/State/Zip Oklahoma City, OK 73112

(Note: Locate well on Section Plat on reverse side)

Contact Person Gerald Smith

Nearest lease or unit boundary line 330 feet

Phone 405-848-5808

County Clark

CONTRACTOR: License # 6033

Lease Name Waits Well # 2-34

Name Martin Drilling Co.

Ground surface elevation 2140 feet MSL

City/State Wichita, Kansas

Domestic well within 330 feet: yes X no

Well Drilled For: Well Class: Type Equipment:

Municipal well within one mile: yes X no

X Oil SWD Infield Mud Rotary

Depth to bottom of fresh water 120

X Gas Inj Pool Ext Air Rotary

Depth to bottom of usable water 200

OWWO Expl Wildcat Cable

Surface pipe by Alternate: 1 X 2

If OWWO: old well info as follows:

Surface pipe planned to be set 700

Operator

Conductor pipe required n/a

Well Name

Projected Total Depth 6600 feet

Comp Date Old Total Depth

Formation Arbuckle

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 9/19/86 Signature of Operator or Agent [Signature] Title as agent

For KCC Use:

Conductor Pipe Required 200 feet; Minimum Surface Pipe Required 200 feet per Alt.

This Authorization Expires 9-19-87 Approved By [Signature] 9-19-86

Move in 10-8-86 set 700' of 8" set 16" @ 2160'

SW. NW SW Sec. 34 Twp. 31 S. Rg. 22 West

Last circulation @ 200'

PLUGGING PROPOSAL IF ABOVE IS D & A.

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with columns for plug depth, cement class, and mousehole details. Includes handwritten notes like 'Top of Arbuckle' and 'Class H-2%'.

RECEIVED STATE CORPORATION COMMISSION CONS. DIV. WICHITA, KS

OCT 24 1986

Vertical list of well data: PUSHER MERVIN JELIAN, TD 6650, SURFACE PIPE 8 5/8 @ 900, ANHYDRITE 1400, STARTING TIME & DATE 10:15 AM 10-22-86, COMPLETION TIME & DATE 10:15 AM 10-22-86, 1st PLUG @ 6650 FT. W/ 5" SX, 2nd PLUG @ 1400 FT. W/ 4" SX, 3rd PLUG @ 780 FT. W/ 4" SX, 4th PLUG @ 40-0 FT. W/ 1" SX, RAT HOLE CIRCULATED W/ 1" SX, MOUSE HOLE CIRCULATED W/ 1" SX, WATER WELL PLUGGED W/ Class H cement, CEMENT COMPANY Halliburton, TECHNICIAN Paul Smith, No one saw.