

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-025-20,693-0000

TECHNICIAN'S PLUGGING REPORT

SW-NE SEC. 18, T31S, R23W/E

1675 FEET FROM N/E SECTION LINE

1625 FEET FROM W/E SECTION LINE

OPERATOR LICENSE # 7381

LEASE NAME Flore Abell WELL # 1

OPERATOR: Mitchell Energy Corp.
NAME & ADDRESS: P.O. Box 4000
Woodlands
77380

COUNTY Clark

WELL TOTAL DEPTH 5781 \$187.88 FEET

CONDUCTOR PIPE: SIZE _____ FEET _____

SURFACE CASING: SIZE 8 1/2" FEET 623

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A

OTHER WELL AS HEREINAFTER INDICATED This well was completed but wouldn't prod.

PLUGGING CONTRACTOR Patrick Well Service Inc. LICENSE NUMBER 7547

ADDRESS Liberal Kansas 67901

COMPANY TO PLUG AT: HOUR: 4:00 P.M. DAY: 4 MONTH: 8 YEAR: 19 83

PLUGGING PROPOSAL RECEIVED FROM George Jackson

(COMPANY NAME) Mitchell Energy Corp. (PHONE) _____

WERE: 1st cast iron bridge plug @ 4100' w/ 2 shx cement on top, 2nd plug @ 1500' w/ 50 shx cement, 3rd plug @ 670' w/ 50 shx cement, 4th plug @ 40' to 0' on solid bridge w/ 10 shx cement. The plugging accomplished by Halliburton, Co. w/ 60/40 gogg w/ 2% gall & 3% cc.

PLUGGING PROPOSAL RECEIVED BY Paul A. Luthis (TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL _____ PART _____ NONE

OPERATIONS COMPLETED: HOUR 8:30 P.M. DAY: 4 MONTH: 8 YEAR: 19 83

ACTUAL PLUGGING REPORT This hole was plugged as proposed.

REMARKS: They had set 5 1/2" to 5780'. They recovered 2730' of 5 1/2" production pipe.

RECEIVED
STATE CORPORATION COMMISSION
AUG 15 1983
8-15-83
CONSERVATION DIVISION
Wichita, Kansas

I ~~did~~ DID NOT OBSERVE THIS PLUGGING.

SIGNED Paul A. Luthis (TECHNICIAN)

INVOICED

DATE 8-18-83

INV. NO. 5220-W

FORM CP-2/3
REV. 6-83