

To: 1 090195
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

AP.I NUMBER 15- Drilled 8/11/76
NW NW, SEC. 2, T. 31 S, R. 24 W/E
4620 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123
Operator: Pickrell Drilling Company, Inc.
Name & Address 110 N. Market, Suite 205
Wichita, KS 67202

Lease Name Ardrey Well # B-1
County Clark 182.85
Well Total Depth 5626 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 347

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635
Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 10:30 a.m. Day: 6 Month: 5 Year: 19 92

Plugging proposal received from Gary Burke
(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

Work: 4 1/2" at 5614' w/150 sx cement, PBTD 5562', Perfs at 5451-61'
1st plug sand back to 5400' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and
150 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 11 a.m. Day: 6 Month: 5 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 5400' and dumped 4 sx cement on top of sand
through bailer,
2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 150 sx cement.
Maximum pressure 800 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2714' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

~~(I did not observe this plugging.)~~

DATE 5-22-92
INV. NO. 35312

Signed [Signature]
(TECHNICIAN)

STATE CORPORATION COMMISSION
57-92
MAY 7 1992