

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM

(PLEASE TYPE FORM and File ONE Copy)

15-189-10148000

API # NA (SPUD 02/37) (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549  
(owner/company name) (operator's)

ADDRESS P.O. BOX 351 CITY LIBERAL

STATE KANSAS ZIP CODE 67905-0351 CONTACT PHONE (316) 624-6253

LEASE CAVNER WELL# 1-33 SEC. 33 T. 31S R. 38 (XXXX/West)

- - - SW SPOT LOCATION/OQQQ COUNTY STEVENS

1320 FEET (in exact footage) FROM (S)N (circle one) LINE OF SECTION (NOT Lease Line)

1320 FEET (in exact footage) FROM E(W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET#

CONDUCTOR CASING SIZE  SET AT  CEMENTED WITH  SACKS

SURFACE CASING SIZE 10-3/4" SET AT 557' CEMENTED WITH 90 SACKS

PRODUCTION CASING SIZE 7" SET AT 2424' CEMENTED WITH 100 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SET: 5-1/2" SLOTTED LINER 2424-2638'

ELEVATION 3150' / -- T.D. 2638' PBDT 2638' ANHYDRITE DEPTH NA  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING MIRU PU SET CIBP @ 2400'. SPOT 2 SXS CMT ON CIBP. CIRC HOLE W/9 PPG MUD. PERF CMT HOLES FROM 607-608'. EMP 88 SXS CMT DWN PROD. CSG/SURFACE CSG ANNULUS. SION. TIH W/TBG & SPOT CMT PLUG FROM 630-507, USE 17 SXS CMT. PULL UP HOLE & SPOT CMT PLUG FROM 53' TO SURFACE, USE 7SXS CMT. CUT OFF 10-3/4" & 7" CSG 3' BELOW GL. CAP WELL. INSCRIBE CAP. RDMO PU. RESTORE LOCATION

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? YES

If not explain why? LOGS SUBMITTED W/ ORIG. COMPLETION REPORT OR DRILLER'S LOG

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

MR. DAVE GILMORE PHONE# (316) 544-7240

ADDRESS P.O. BOX 308 City/State HUGOTON, KANSAS 67951

PLUGGING CONTRACTOR HALLIBURTON ENERGY SERVICES KCC LICENSE # 5287  
(company name) (contractor's)

ADDRESS BOX 1598, LIBERAL, KS 67905-1598 PHONE # (316) 624-3879

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 8/15/97 AUTHORIZED OPERATOR/AGENT: John A. Broman  
JOHN A. BROMAN (Signature) DIV. PROD. ENG.

8-20-97

10/11/97 RECEIVED  
KANSAS CORP COM.  
1997 AUG 20 4 11:46

**ANADARKO PETROLEUM CORPORATION**

PHONE 316 - 624 - 6253 . 1701 NORTH KANSAS AVE. . P.O. BOX 351 . LIBERAL, KANSAS 67905 - 0351



August 15, 1997

Kansas Corporation Commission  
Conservation Division  
Finney State Office Building  
130 South Market, Rm. 2078  
Wichita, Kansas 67202

Attn: Mr. Jeff Klock

Re: Well Plugging Application Form (Form CP-1)

Cavner 1-33  
Sec. 33-31-38  
Stevens County, Kansas

Spikes "B" No. 2H  
Sec. 22-31S-38W  
Stevens County, Kansas

Dear Jeff:

Enclosed in duplicate is a well plugging application (Form CP-1) for each of the referenced wells. Upon approval of these applications, please notify this office at the letterhead address so that plugging operations may commence.

Very truly yours,

John A. Broman  
Division Production Engineer  
AMC/sjc

Enclosures

cc: Well Files  
L. M. Harvey  
Halliburton Energy Services  
TRC - HGO  
Manager Land Administration - HGO  
WI Owners

kccintpa.doc

RECEIVED  
KANSAS CORP COM  
1997 AUG 20 A 11:46



## Kansas Corporation Commission

Bill Graves, Governor Timothy E. McKee, Chair Susan M. Seltsam, Commissioner John Wine, Commissioner  
Judith McConnell, Executive Director David J. Heinemann, General Counsel

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

August 20, 1997

Anadarko Petroleum Corporation  
P O Box 351  
Liberal KS 67905-0351

Cavner #1-33  
API 15-N/A-189-10148-0000  
1320 FSL 1320 FWL  
Sec. 33-31S-38W  
Stevens County

Dear Mr. Dave Gilmore,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely,

A handwritten signature in cursive script that reads "David P. Williams".

David P. Williams  
Production Supervisor

District: #1  
304 W. McArtor  
Dodge City, KS 67801  
(316) 225-6760