

SEP 15 1994

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 03/92

15-129-00082-0000

CONSERVATION DIVISION  
WICHITA, KS

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # \_\_\_\_\_ (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR AMOCO PRODUCTION COMPANY KCC LICENSE # 5952  
(owner/company name) (operator's)

ADDRESS P. O. BOX 800 ROOM 925 CITY DENVER

STATE \_\_\_\_\_ CO. \_\_\_\_\_ ZIP CODE 80201 CONTACT PHONE # (303) 830-5130

LEASE MORGAN GU /CG WELL# 1 SEC. 7 T.31S R. 39 (East/West)

SPOT LOCATION/QQQQ COUNTY MORTON

1980 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

1980 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL \_\_\_\_\_ GAS WELL X D&A \_\_\_\_\_ SWD/ENHR WELL \_\_\_\_\_ DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 9 5/8" SET AT 723' CEMENTED WITH 500 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 2907' CEMENTED WITH 220 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: \_\_\_\_\_

ELEVATION 3222 T.D. 6110 PBDT 2834 ANHYDRITE DEPTH 1760  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD \_\_\_\_\_ POOR \_\_\_\_\_ CASING LEAK X JUNK IN HOLE \_\_\_\_\_

PROPOSED METHOD OF PLUGGING \_\_\_\_\_

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? YES

If not explain why? WELL LOGS NOT AVAILABLE - TOP OF ZONES PICKED FROM OFFSET.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

JOE EUDEY \_\_\_\_\_ PHONE# \_\_\_\_\_ (316) 356-6981 \_\_\_\_\_

ADDRESS 2225 OKLAHOMA AVE City/State ULYSSES, KS 67880

PLUGGING CONTRACTOR HALLIBURTON KCC LICENSE # \_\_\_\_\_  
(company name) (contractor's)

ADDRESS P O BOX 598, LIBERAL, KS 67905 PHONE # (316) 624-2879 \_\_\_\_\_

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) \_\_\_\_\_

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 9/12/94 AUTHORIZED OPERATOR/AGENT: Ellen Hartley  
(signature)

6/95

11

**Subject: Plugging Procedure  
Morgan Gas Unit CG #1  
Sec 7-T31S-R39W  
Morton County, Kansas**

**Date: September 2, 1994**

**Operator: Amoco Production Company  
P.O. Box 800  
Denver, CO 80201**

**Procedure:**

- 1- POOH w/ Tbg. and Rods.
- 2- RIH w/ CIBP and set @ +/- 2700', above the perforations.  
Perfs: 2710'-2716', 2734'-2738', 2752'-2762', 2770'-2780', 2793'-2796'.
- 3- Pump two SX of class H cement on CIBP.
- 4- RIH w/ second CIBP and set on top of Glorieta zone @ +/- 1200'.  
Glorieta top: 1230'
- 5- RIH w/ 3 3/8" csg gun, loaded w/ 15 gram charges, 4SPF 90 degree phasing.  
Perforate Production Casing from 680'- 682'.
- 6- Pump 322 SX of 16.4 lbs/gal of class H cement to cement the production casing to surface (Squeeze volume 219 sx, production csg cement plug volume 103 sx).
- 7- Please contact KCC representative 48 hours in advance.
- 8- If you have any questions or coments regarding the procedure, please contact  
Sonia Vahedian @ 303/830-5867.

**RECEIVED**  
KANSAS CORPORATION COMMISSION

SKV

**SEP 15 1994**

CONSERVATION DIVISION  
WICHITA, KS



## Kansas Corporation Commission

Joan Finney, Governor   Susan M. Seltsam, Chair   F.S. Jack Alexander, Commissioner   Rachel C. Lipman, Commissioner  
Judith McConnell, Executive Director   Brian Moline, General Counsel

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

September 15, 1994

Amoco Production Company  
P O Box 800 Room 925  
Denver CO 80201

Morgan GU/CG #1  
API 15-N/A 129-00032-0000  
1980 FSL 1980 FWL  
Sec. 07-31S-39W  
Morton County

Dear Joe Eudey,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams  
Production Supervisor

District: #1  
304 W. McArtor  
Dodge City KS 67801  
(316) 225-6760