

SEP 15 1994

CONSERVATION DIVISION
WICHITA, KS

WELL PLUGGING APPLICATION FORM

(PLEASE TYPE FORM and File ONE Copy)

API # 15-129-00502 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR AMOCO PRODUCTION COMPANY KCC LICENSE # 5952
(owner/company name) (operator's)

ADDRESS P. O. BOX 800 ROOM 925 CITY DENVER

STATE _____ CO. _____ ZIP CODE 80201 CONTACT PHONE # (303) 830-5130

LEASE GILLESPIE GAS UNIT WELL# 1 SEC. 8 T.31S R. 39 (East/West)

CENTER OF LOCATION _____ SPOT LOCATION/QQQQ _____ COUNTY MORTON

2640 _____ FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

2640 _____ FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL _____ GAS WELL X _____ D&A _____ SWD/ENHR WELL _____ DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 593 CEMENTED WITH 350 SACKS

PRODUCTION CASING SIZE 5 1/2" SET AT 2611' CEMENTED WITH 350 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 2421-2470; 2488-2527; 2555-2586;

ELEVATION 3213 T.D. 2645 PBDT 2630 ANHYDRITE DEPTH 1750-1790
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD _____ POOR _____ CASING LEAK X JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING _____ SEE ATTACHED _____

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? YES

If not explain why? WELL LOGS NOT AVAILABLE - TOP OF ZONES PICKED FROM OFFSET.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

MELANIE HILL PHONE# (316) 356-7059

ADDRESS 2225 OKLAHOMA AVE City/State ULYSSES, KS 67880

PLUGGING CONTRACTOR HALLIBURTON KCC LICENSE # _____
(company name) (contractor's)

ADDRESS P O BOX 598, LIBERAL, KS 67905 PHONE # (316) 624-2879

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) _____

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 9/14/94 AUTHORIZED OPERATOR/AGENT: Ellen Hartley
(signature)

Subject: Plugging Procedure
Gillespie Gas Unit #1
Sec 8-T318-R39W
Morton County, Kansas

Date: September 1, 1994

Operator: Amoco Production Company
P.O. Box 800
Denver, CO 80201

Procedure:

- 1- POOH w/ Tbg. and Rods.
- 2- RIH w/ CIBP and set @ +/- 2350', above the perforations.
Perfs: 2421'-2470', 2488'-2527', 2555'-2586'.
- 3- Pump two SX of class H cement on CIBP.
- 4- RIH w/ second CIBP and set on top of Glorieta zone @ +/- 1150'.
Glorieta: 1230' - 1500'
- 5- RIH w/ 3 3/8" csg gun, loaded w/ 15 gram charges, 4SPF 90 degree phasing.
Perforate Production Casing from 570'- 572'.
- 6- Pump 260 SX of 16.4 lbs/gal of class H cement to cement the production casing to surface (Squeeze volume 112 sx, production csg cement plug volume 148 sx).
- 7- Please contact KCC representative 48 hours in advance.
- 8- If you have any questions or coments regarding the procedure, please contact
Sonia Vahedian @ 303/830-5867.

SKV

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 15 1994

CONSERVATION DIVISION
WASHINGTON



Kansas Corporation Commission

Joan Finney, Governor Susan M. Selsam, Chair F.S. Jack Alexander, Commissioner Rachel C. Lipman, Commissioner
Judith McConnell, Executive Director Brian Moline, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

September 15, 1994

Amoco Production Company
P O Box 800 Room 925
Denver CO 80201

Gillespie Gas Unit #1
API 15-N/A
C
Sec. 08-31S-39W
Morton County

Dear Melanie Hill,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City KS 67801
(316) 225-6760