

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-017-20127-0001

LEASE NAME Coslet 1-34

WELL NUMBER 1-34
150' east of center
SPOT LOCATION of SW of SW

SEC 34 TWP 31S RGE 5 XXX or (W)

COUNTY Harper

Date Well Completed 10-31-83

Plugging Commenced 2-12-86

Plugging Completed 2-13-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Sho-Bar Energy, Inc.

ADDRESS Box 217 Harper, Ks. 67058

PHONE # 316 896-2710 OPERATORS LICENSE NO. 7944

Character of Well Some oil-washdown
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Wichita

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation Simpson (before washdown) Depth to top _____ bottom Rotary T.D. 3370'

Show depth and thickness of all water, oil and gas formations. Perfs: no higher than 3303'.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	217	8 5/8	217'	0
		217		4 1/2		71 jts.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

2-12-86 Rigged, bottom flag 2780', fillup at 2880' / Dumped 5 sx. cement, cut casing at 2535'. Sargeant cut casing, recovered 71 jts.
2-13-86 Rigged down, moved off.


Plugging: sand up to 3250', 50' above perfs. 5 sx. cement on top of sand. Pump in top hole, 15 sx. gel, 3 sx. hulls, 115 sx. cement to top. Top hole plugging: 3 sx. hulls, 15 gel, 115 sx. cement. (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service, Inc. License No. 5893
Address Box 847 Pratt, Ks. 67124

STATE OF Kansas COUNTY OF Pratt, ss.

Judy Berry (employee of operator) or plugging contractor
of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry
(Address) Box 847 Pratt, Ks.



SUBSCRIBED AND SWORN TO before me this 24 day of Feb., 1986

My Commission expires: Feb. 6, 1989

Dorothy M. Ferguson
STATE CORPORATION COMMISSION Notary Public
FEB 27 1986 2-27-86