

STATE OF KANSAS
STATE CORPORATION COMMISSION


15-119-20604-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Meade County, Sec. 28 Twp. 31S Rge. 28 ~~EEW~~
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines
SW NE

Lease Owner IREX Corporation
Lease Name Fisher Well No. #1
Office Address 1670 Broadway - Suite 3301, Denver, CO 80202
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plot

Dry Hole
Date Well completed 4-29-83 19
Application for plugging filed 4-29-83 19
Application for plugging approved 4-29-83 19
Plugging commenced 4-29-83 19
Plugging completed 4-29-83 19
Reason for abandonment of well or producing formation

Commercial quantities of oil not found
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant
Producing formation Depth to top Bottom Total Depth of Well 5800'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1518'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Plug @ 1560' w/50 sx.
Plug @ 1020' w/40 sx.
Plug @ 40' w/10 sx.
Rat Hole .15 sx.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co., Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Wilson Rains, President of Rains & Williamson Oil Co., Inc. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) *Wilson Rains*
435 Page Court, 220 W. Douglas, Wichita, Ks. 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 3 day of May, 19 83



Juanita M. Green
Juanita M. Green Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

MAY 20 1983

CONSERVATION DIVISION
Wichita, Kansas

DRILLER'S LOG

15-119-20604-0000

COMPANY: IREX Corporation

SEC. 28 T. 31S R. 28W

WELL NAME: Fisher #1

LOC. SW NE

COUNTY: Meade

RIG NO. #2

TOTAL DEPTH 5800'

ELEVATION

COMMENCED: 4-15-83

COMPLETED: 4-29-83

CONTRACTOR: Rains & Williamson Oil Co., Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 1518' w/600 sx. Lite, 2% cc. and 200 sx. Class H, 3% cc.

PRODUCTION: D&A

LOG

(Figures Indicate Bottom of Formations)

Sand	430
Sand & Shale	930
Shale	1050
Sand	1165
Shale	1521
Shale & Sand	3195
Shale & Lime	3385
Shale & Sand	3605
Lime	4060
Shale & Lime	4450
Lime & Sand	4635
Lime	4995
Lime & Shale	5172
Lime	5322
Lime & Shale	5430
Lime	5800
<u>ROTARY TOTAL DEPTH</u>	<u>5800</u>

RECEIVED
STATE CORPORATION COMMISSION

MAY 20 1983

CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas)
COUNTY OF Sedgwick)

SS:

I, Wilson Rains, President of Rains & Williamson Oil Co., Inc.
upon oath state that the above and foregoing is a true and correct copy of the log of the
Fisher #1 well.

Wilson Rains
Wilson Rains



Subscribed and sworn to before me this 3 day of May, 1983.

My Appointment Expires:
10-4-83

Juanita M. Green
Juanita M. Green