

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

X Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 5316 EXPIRATION DATE 6/30/83

OPERATOR Falcon Exploration Co., Inc. API NO. 15-151-21,181-60-40

ADDRESS 1531 KSB&T Building COUNTY Pratt

Wichita, Kansas 67202 FIELD

\*\* CONTACT PERSON Mike Mitchell- PROD. FORMATION

PHONE 316 262-1378

PURCHASER Clear Creek, Inc. LEASE Hissons

ADDRESS P. O. Box 1045 WELL NO. 2

McPherson, Kansas 67460 WELL LOCATION C W/2 NW SW

DRILLING Graves Drilling Co., Inc. 330 Ft. from West Line and

CONTRACTOR ADDRESS 910 Union Center 660 Ft. from North Line of

Wichita, Kansas 67202 the SW (Qtr.) SEC 2 TWP 28SRGE 12W.

PLUGGING CONTRACTOR ADDRESS

WELL PLAT

(Office Use Only)


KCC  KGS

SWD/REP  PLG

TOTAL DEPTH 4550' PBD 4151'

SPUD DATE 8-16-82 DATE COMPLETED 8-29-82

ELEV: GR 1792' DF 1800' KB 1803'

DRILLED WITH (CABLE) (ROTARY) (XXX) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE

Amount of surface pipe set and cemented 279' w/ 175 DV Tool Used?

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - (Oil) Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.


A F F I D A V I T

Micheal S. Mitchell, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

*Micheal S. Mitchell*  
(Name)

SUBSCRIBED AND SWORN TO BEFORE ME this 28th day of September, 1982, 19 82.



*Patricia L. Easter*  
(NOTARY PUBLIC)

MY COMMISSION EXPIRES: October 5, 1983

RECEIVED STATE CORPORATION COMMISSION SEP 29 1982

CONSERVATION DIVISION Wichita, Kansas

\*\* The person who can be reached by phone regarding any questions concerning this information.

**FILL IN WELL LOG AS REQUIRED:**

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
			NAME	DEPTH
Sand	0	40	Base Admire	2600 (-797)
Sand & red bed	40	278	Ind. Cave Sd.	2611 (-808)
			Ind. Cave Sd.	2621 (-818)
Red bed	278	502	Wab.	2651 (-848)
			Stotler	2786 (-983)
Red bed & shale	502	1658	Howard	2957 (-1154)
			Topeka	3098 (-1295)
Shale	1658	1875	Hb.	3471 (-1668)
			Brown Lime	3655 (-1852)
Shale & lime	1875	4550	L/KC	3670 (-1867)
Rotary Total Depth		4550		

**RELEASED**  
SEP 01 1963  
**FROM CONFIDENTIAL**

**Report of all strings set-- surface, intermediate, production, etc. CASING RECORD (New) or (Used)**

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	13-3/4"	10-3/4"	42#	279'	common	175	2% Ge1, 3% CC
Production	7-7/8"	4 1/2"	10.5#	4168'	common	150	10 bbl. salt preflush

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4		4058-4060

TUBING RECORD		
Size	Setting depth	Packer set at
2 3/8"	4136'	

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated
250 Gal. 7 1/2% Acid, 65 Bbls. SW	

Date of first production 9/11/82	Producing method (flowing, pumping, gas lift, etc.)	Gravity
<b>RATE OF PRODUCTION PER 24 HOURS</b>	Oil bbls.	Gas MCF
	Water %	Gas-oil ratio bbls. CFPB
Disposition of gas (vented, used on lease or sold)		Perforations