

API NUMBER 15-189-223290000

LEASE NAME HJV CENTRAL LIFE "A"

WELL NUMBER 1

2160 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 4 TWP. 33 RGE 35 ( E ) or ( W )

COUNTY STEVENS

Date Well Completed 1-4-2000

Plugging Commenced 1-5-2000

Plugging Completed 1-5-2000

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # ( 316 ) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-5-2000 (date)

by MR. STEVE MIDDLETON (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation NONE Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 6500

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	1729'	NONE

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set. L.H. W/4 1/2" DP TO 3140' & SPOT 100 SKS 60/40 POZMIX, 6%GEL @ 3140', TOH TO 1760' & SPOT 50 SKS, TOH TO 650' & SET 40 SKS, TOH TO 40' & SET 10 SKS FROM 40' TO 0'. SET 10 SKS IN MH & 15 SKS IN RH. CUT OFF 8-5/8" CSG 3' BELOW GL AND CAP, PERMANENTLY INSCRIBE WELL NAME, NUMBER AND DATE PLUGGED ON CAP.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor HALLIBURTON ENERGY SERVICES License No. 5287

Address P.O. BOX 1598, LIBERAL, KANSAS 67905-1598

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

L. MARC HARVEY, DRILLING TECHNICAL ASSISTANT (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) L. Marc Harvey 1-26-2000


L. MARC HARVEY, DRILLING TECHNICAL ASSISTANT  
 (Address) P.O. BOX 351, LIBERAL, KS 67901-0351

RECEIVED  
 STATE CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 26<sup>th</sup> day of January, 19 99

IAN 28 2000  
 1-28-00  
 CONSERVATION DIVISION  
 Wichita, Kansas

My Commission Expires: \_\_\_\_\_



REGION North America	NWA/COUNTRY MidCont USA	BDA / STATE Ks	COUNTY Stevens
MBU ID / EMP # NICK10110 106328	EMPLOYEE NAME Nick Karbe	PSL DEPARTMENT 21	
LOCATION Liberal	COMPANY A.P.C.	CUSTOMER REP / PHONE Jim Barlow	
TICKET AMOUNT \$ 4146.44	WELL TYPE 02	API / UWI #	
WELL LOCATION NW of Woods	DEPARTMENT Cement	JOB PURPOSE CODE 115	
LEASE / WELL # HJV Central Life A-1	SEC / TWP / RNG 9-335-35W		

HES EMP NAME/EMP#/(EXPOSURE HOURS)	HRS	HES EMP NAME/EMP#/(EXPOSURE HOURS)	HRS	HES EMP NAME/EMP#/(EXPOSURE HOURS)	HRS	HES EMP NAME/EMP#/(EXPOSURE HOURS)	HRS
N. Karbe	106328	6					
S. Engel	106099	6					
M. Restro		6					

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL)(GAL)	PUMPS		PRESS. (psi)		JOB DESCRIPTION / REMARKS
				T	C	Tbg	Csg	
	1100							called out on loc
	1500							Held safety mty Set up trks
	1604					1700		1st Plug @ 3140'
	1609	2	0			125		1st lines st wtr ahead
	1611	6	10/0			325		st cmt 100 sks @ 13.5"
	1615	3.5	27/0			50		st wtr behind
	1617	7	3.5/0			200		st mud
	1622		34			0		plug balanced
	1725	5.5	0			150		2nd plug @ 1760'
	1727	5.5	10/0			150		st wtr ahead
	1730	4.5	13.7/0			0		st cmt 50 sks @ 13.5"
	1731	5.5	3.5/0			100		st wtr behind
	1734		18			0		st mud
	1819	7	0			100		plug balanced
	1824	5.5	18/0			100		2nd plug @ 650'
	1826	4.5	11/0			0		3rd wtr
	1828		6.5			0		st cmt
	1957	1.5	0					st wtr
	2001	1.5	6/0					end plug balanced
	2002		2.5					4th plug @ 46'
	2006	1.5	0/3.5			25		st wtr
	2010	1.5	0/2.5			25		st cmt
								end Plug RH Plug MH

Job complete  
Thank you  
Nick & Crew

RECEIVED  
STATE CORPORATE TAX COMMISSION  
JAN 28 2000  
CONSERVATION DIVISION  
Wichita, Kansas

