

NE 1/4 of SE 1/4

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

COPY

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-189-21123-0000 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR ARCO Oil and Gas Company OPERATOR'S LICENSE NO. 5398

ADDRESS 5815 Oklahoma Ave., Woodward, OK 73801 PHONE # (405) 256-3369

LEASE (FARM) Baughman WELL NO. 2 WELL LOCATION 660' FEL COUNTY Stevens

SEC. 21 TWP. 33 RGE. 35 ~~XXXX~~ (W) TOTAL DEPTH 6500' PLUG BACK TD 6119'

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 1785.5' CEMENTED WITH 800 SACKS

CASING SIZE 5-1/2" SET AT 6497' CEMENTED WITH 370 SACKS

PERFORATED AT 6028-35'

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set CIBP @ 6015' w/4 sx cement on top of CIBP. Cut off

5-1/2" casing at 1800' & spot 75 sx plug 50' below 8-5/8" casing and 50' up into

surface casing. Spot 30' plug in 8-5/8" 3' to 33'.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 9/10/90 @ 8:00 A.M.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Roger Flummerfelt PHONE # (316) 356-3546

ADDRESS P. O. Box 574, Ulysses, Kansas 67880

PLUGGING CONTRACTOR Dowell Schlumberger, Inc. LICENSE NO. 116095

ADDRESS P. O. Box 887 Ulysses, Kansas 67880 PHONE # (316) 356-1272

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

DEC 27 1990

CONSERVATION DIVISION
Wichita, Kan. 67202

SIGNED:

D. L. Mashburn
(Operator or Agent) D. L. Mashburn

DATE:

August 9, 1990