

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail For Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

PRATT

County. Sec. 13 Twp. 28 Rge. 12 (X) W (W)

Location as "NE/CNW%SW%" or footage from lines C NE

Lease Owner PETROLEUM, INC.

Lease Name MILLER "K" Well No. 1

Office Address Route 2, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed September 20, 19 57

Application for plugging filed September 25, 19 57

Application for plugging approved September 20, 19 57

Plugging commenced September 20, 19 57

Plugging completed September 20, 19 57

Reason for abandonment of well or producing formation

No producible Zone

If a producing well is abandoned, date of last production None 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M.A. Rives Box 8, Pratt, Kansas

Producing formation ----- Depth to top --- Bottom --- Total Depth of Well 3215 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	335.14'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud up with heavy mud to 300' followed by wooden plug. Placed 20 sacks cement through drill pipe on to plug. Mud up to 35' and placed 1/4 sack hulls at 35' followed by wooden plug and 10 sacks cement to base of well cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company

Address Route 2, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

Don Searle (employee of owner) or (Notary Public) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle

Route 2, Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of September 19 57

Notary Public.

My commission expires July 11, 1960

PLUGGING
FILE SEC 13 T 28 R 12 W
BOOK PAGE 47 LINE 39

RECEIVED
STATE CORPORATION COMMISSION

SEP 27 1957 9-27-57

CONSERVATION DIVISION

WELL LOG

COMPANY PETROLEUM, INCORPORATED

SEC. 13 T. 28S R. 12W

FARM MILLER "K" NO. 1


LOC. C/NE/4

TOTAL DEPTH 3215'

COUNTY Pratt Co., Kansas

COMM. September 9, 1957 COMP. September 20, 1957

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8 5/8" @ 345.14' W/275 sax.

ELEVATION 1835' DF

PRODUCTION Plugged & Abandoned

FIGURES INDICATE BOTTOM OF FORMATIONS

35	Clay
210	Sand
347	Red bed
1085	Red bed & shells
1735	Shale & shells
2100	Lime
3190	Lime & shale
3195	Lime
3215	Shale & lime
3215	T. D.

Lost circulation zone, lost hole.

RECEIVED
STATE CORPORATION COMMISSION

SEP 27 1957

CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS
County of BARTON

PLUGGING
FILE SEC 13 T. 28 R. 12W
BOOK PAGE 47 LINE 39

I, Verne A. Morris of Garvey Drilling Co.

upon oath state that the above and foregoing is a true and correct copy of the log of the #1k Miller "K" well

Verne A. Morris

Subscribed and sworn to before me this 25th day of September 19 57

My Commission Expires: July 11, 1960

[Signature]
NOTARY PUBLIC