

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-151-21,862 -00-00

LEASE NAME Rosenbaum

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1

2970 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 10 TWP. 28 SRGE. 12 (E) or (W)

COUNTY Pratt

Date Well Completed _____

Plugging Commenced 1-24-90

Plugging Completed 4-19-90

LEASE OPERATOR DEVONIAN OIL CO.

ADDRESS 1246 Mass Lawrence, Kansas 66044

PHONE# (913) 841-4508 OPERATORS LICENSE NO. 4059

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-15-90 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? All ready sent in.

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4480

Plug back TD 3992, all else below squeezed off. Perfs: 3972-76, 3964-70
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				14 3/4 conductor pipe		0
				10 3/4	246'	0
				8 5/8	852'	0
				4 1/2	4480	1508'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set

1-24-90 First plug sand back to 3920' and dump 4 sx cement on top fo sand through bailer,
 2nd plug, pump 4 sx. hulls, 10 sx gel, 50 sx. cement, 10 sx gel, 1 sx. hulls, release
 8 5/8 wiper plug and pump 100 sx. cement. ~~XXXXXX~~

~~XXXXXX~~ If additional description is necessary, use BACK of form.
 bridge with bailer. Second plug pumped down 8 5/8 surface pipe with 400 # hulls (over)

Name of Plugging Contractor PRATT WELL SERVICE, INC. License No. 5893

Address North Highway 61 Pratt, Kansas 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Devonian Oil Co.


STATE OF Kansas COUNTY OF Pratt, ss.

Judy Berry (Employee of plugging contractor) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) Box 847 - Pratt, Ks.

SUBSCRIBED AND SWORN TO before me this 30th day of April, 19 90



My Commission Expires: February 6, 1993 Notary Public

4-19-90

10 sx. gel, 50 sx. cement, 10 sx. gel, 100# hulls, released 8 5/8 wiper plug and pumped 100 sx. cement. Max pressure 300 psi and shut in 100 psi. Topped out 8 5/8 with 10 sx. cement. 3rd plug, pumped down 10 3/4 x 8 5/8 annulus with 100 sx. cement. Max pressure 300 psi and shut in 200 psi.

on 4-19-90, Pratt Well Service was not represented -
By Ditam did the plug - Steve Pfeifer was present for
the date.

Judy Berry.

