


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-129-16098-0000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Morton County. Sec. 28 Twp. 31 Rge. 43 ~~(W)~~ (W)  
Location as "NE/CNW/SW" or footage from lines. CSW  
Lease Owner Omega Oil Corp.  
Lease Name Uhl Well No. #1  
Office Address 208 LaSalle, Chicago, Ill.  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed 12/31 19 58  
Application for plugging filed 2/19 19 58  
Application for plugging approved 2/20 19 58  
Plugging commenced ~~XXXXXX~~ 2/24/ 19 58  
Plugging completed 3/2/ 19 58  
Reason for abandonment of well or producing formation dry hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Merle Rives, Garden City, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3350 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Hard sand, red bed & gyp		0	677'	8 5/8"	677'	0
Lime & shale		677'	3348'	5 1/2"	3348'	1222

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole back with sand from 2870'W/5 sks cement, 15 sks Jel-mud  
Set rock bridge and dumped 20 sks cement. Mudded hole to 35', dumped  
10 sks cement to base of cellar

RECEIVED  
APR 2 1958  
4-2-58  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Southwest Casing Pulling Co., Inc.  
Address P.O. Box 364, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Owen Woodland (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. Graham-Michaelis Drlg. co.  
(Signature) Owen Woodland  
211 North Broadway, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of March, 19 58

J.D. Grier

Notary Public.

My commission expires 1-7-61

PLUGGING  
FILE SEC 28 T. 31 R. 43a  
BOOK PAGE 84 LINE 14

UHL #1

15-129-10096-0000

Well Record

Location: C SW/4 Section 26-T31S-R43W Commenced: Dec. 22, 1957  
Morton County, Kansas Completed: Dec. 31, 1957  
(rotary)

Operator: Omega Oil Corporation  
Room 1988  
208 South LaSalle Street  
Chicago, Illinois

Contractor: Graham-Michaelis Drilling Co.  
311 North Broadway  
Wichita, Kansas

Casing Records: 6 5/8" 6877° W/300 sacks cement  
& 1/2" 3348° W/700 gal. cement

LOG

Soil & Clay	40
Hard Sand & Gyp	310
Sand & Gyp	372
Red Bed, Sand & Shale W/Gyp	475
Sand Soft	491
Hard Sand, Red Bed & Gyp	685
Red Bed	680
Hard Sand, Gyp & Red Bed	1045
Gyp	1100
Sand	1280
Red Bed, Shale & Gyp	1905
Red Bed & Anhydrite	2205
Red Bed, Shale & Lime	2360
Lime & Shale W/Streaks Anhydrite	2555
Lime, Anhydrite & Shale	2640
Lime & Shale	3015
Doln & Shale	33040
Lime & Shale W/Silt Streaks	3141
Lime & Shale	3210
Lime	3282
Lime & Shale	3242
Lime	3360. STD.

RECEIVED  
APR 2 1958  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
) ss.  
COUNTY OF SEDGWICK)

The undersigned, GRAHAM-MICHAELIS DRILLING COMPANY, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Report.

GRAHAM-MICHAELIS DRILLING COMPANY

By John L. James  
John L. James, Geologist.

Subscribed and sworn to before me  
this 6th day of January, 1958.

J. D. Greer  
My commission expires: 1/7/61

PLUGGING  
FILE SEC 25T 31R 43W  
BOOK PAGE 84 LINE 14