


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Seward County, Sec. 6 Twp. 31S Rge. 8X34 (W)
Location as "NE/CNW/SW" or footage from lines SW NE
Lease Owner Texaco Inc.
Lease Name Anna Day O/A Well No. 2
Office Address 614 Bitting Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 8-16-19 64
Application for plugging filed 8-18-19 66
Application for plugging approved 8-19-19 66
Plugging commenced 8-25-19 66
Plugging completed 8-26-19 66
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 5-6- 19 66
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well E. Eves, Box "F" Sublette, Kansas
Producing formation Morrow Depth to top 5397 Bottom 5404 Total Depth of Well 5550 Feet
Show depth and thickness of all water, oil and gas formations. PBTD 5440

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Morrow	Oil	5398	5404	8-5/8"	663'	None
				5-1/2"	5550'	908'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole plugged as follows: 5440-5200 w/25 sxs cmt,
5200-650 w/hvy mud,
650-550 w/35 sxs cmt,
550-30 w/hvy mud,
30-0 w/10 sxs cmt.

Complete 5 PM 8-26-66.

RECEIVED
STATE CORPORATION COMMISSION
SEP 28 1966
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargent's Casing Pulling Service
Address 121 West 9th Street, Liberal, Kansas 67901

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
M. R. Wilson (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. R. Wilson
614 BITTING BUILDING, WICHITA, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of September, 19 66

Leggy Sue Jones
Notary Public.

My commission expires 10-13-69

TEXACO INC.—LOG OF WELL

Tulsa DIVISION

INDICATE EXACT WELL LOCATION & LEASE BOUNDARY WITHIN SECTION

WELL Anna Day O/A No. 2 L. D. FILE NO. #110060

LOC. SW NE SEC. 6 TWP. 31S RGE. 34W

DIST. Wichita CO. PARISH Seward STATE Kansas

COMM. DRLG. 7-9-64 COMP. DRLG. 5550 DAYS DRLG. 22

ROT. FROM 0 TO 5550 CABLE FROM TO

CONTR. OR CO. RIG NO. D & M Drilling Co. T. D. DRILLED 5550

COMP. T. D. 5440 ZERO ELEV. GRD. ELEV. 2867 CSG. FLG. ELEV.

DATE OF FIRST PROD. 8-14-64 OFFICIAL COMP. DATE 8-16-64

LOGS RUN Dual Induction-Lateralog & Sonic & Dipmeter & Correlation

CASING RECORD

SIZE INCHES	DEPTH FEET	WEIGHT #/FT.	GRADE	RANGE	REMARKS—QUAN. CMT., TEMP. SURV., ETC.
8-5/8	633	26#	SR		Set & cmtd 8-5/8" csg @ 633 w/175 sx Common 12% gel & 2% CaCl ₂ followed w/130 sx Common 2% CaCl ₂ . Cmt did not cure. Found cmt @ 180'. Prep to run 1" along side of 8-5/8" & cmt to surface.
5-1/2					Set & cmtd 5-1/2" csg @ 5550 w/60 sx Common 20% Diacel "D" & 100 sx slit bat Poz w/0.75% CFR-2 & 100 sx Common 40% Diacel "D" thru DV tool @ 1730.

COMPLETION DATA

FORMATION	Horton		
DATE OF TEST	8-16-64		
DEPTH OF PROD. INTERVAL	5398-5404		
INITIAL PRODUCTION:	OIL - BPD	31	
	GAS - MCF	-	
	WATER - SPD	None	
	GOR	11088/1	
	BHP - PSI	-	
CORRECTED API GRAVITY	39.90		
PRODUCING CONDITIONS	Pumping		
ARTIFICIAL STIMULATION	10 x 10 frag 250 gal Acid		

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 19 1966
 CONSERVATION DIVISION
 Wichita, Kansas

KWL B
 TULSA
 FIELD
 CIVIL SERV.
 (Garrison)
 (Wichita)
 (Duland)

INTERESTS:
 Texaco Inc. 94%
 Columbian Fuel Corp. 6%

REMARKS
 1) 3.65
 2) 750
 700
 600

WELL ANNA DAY O/A No. 2 FIELD CUSTER AREA WICHITA