


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Seward County, Sec 7 Twp 31S Rge. (E) 34 (W)

Location as "NE/CNW/SW" or footage from lines 150' S/C NE SW
Lease Owner Mobil Oil Corporation
Lease Name Marguerite Rooney Well No. 2
Office Address P. O. Box 1934, Oklahoma City, Oklahoma 73101
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed April 9 1965
Application for plugging filed August 20 1973
Application for plugging approved August 22 1973
Plugging commenced October 22 1973
Plugging completed October 23 1973
Reason for abandonment of well or producing formation Uneconomical to produce.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Edgar Eves
Producing formation Morrow Depth to top 5344' Bottom 5570' Total Depth of Well 5700 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Morrow	Oil	5414'	5422'	8-5/8"	643'	None
				4 1/2"	5500'	1220'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Spotted 20 sack cement plug at 5200' - top of cement at 2000'. Shot 4 1/2" casing at 1805', unable to pull casing. Shot 4 1/2" casing at 1400', unable to pull casing. Shot 4 1/2" casing at 1220', pipe was free. Placed 35 sack cement plug from 743' - 643'. Placed 15 sack cement plug in top of 8-5/8" surface casing from 45' - 0'. Cut off 8-5/8" casing 3' below ground level and welded a steel plate across the top of the 8-5/8" casing.

RECEIVED
STATE CORPORATION COMMISSION
NOV 14 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sargents Casing Pulling Service
Address 620 South Lincoln, Liberal, Kansas 67901

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.
Paul K. Langenberg (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul K. Langenberg
Paul K. Langenberg, Office Group Supervisor
P. O. Box 1934, Oklahoma City, Oklahoma 73101
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of November, 1973

My commission expires November 17, 1977

Richard N. Squibb
Notary Public.

MARGUERITE ROONEY NO. 2
C NE SW - SECTION 7 -31S - 34W
SEWARD COUNTY, KANSAS

15-175-10117-0000

WELL RECORD

OPERATOR: MOBIL OIL COMPANY
300 NORTH BROADWAY, WICHITA 2, KANSAS

CONTRACTOR: LOHMANN-JOHNSON DRILLING CO., INC.
320 INDIANA BANK BLDG., EVANSVILLE 8, INDIANA

COMMENCED: JANUARY 28, 1964
COMPLETED: FEBRUARY 15, 1964

CASING: RAN 8-5/8" SURFACE CASING SET @ ~~2~~⁶⁴³ FT. CEMENTED W/
400 SACKS CEMENT
SET 4-1/2" PRODUCTION CASING @ 5500 FT. CEMENTED W/
700 SACKS CEMENT

FROM	TO	FORMATIONS
0	250	SAND
250	643	SAND & RED BED
643	1145	RED BEDS & SAND
1145	1795	RED BED & SAND ANHYDRITE
1795	2019	RED BED & SHALE
2019	2250	SHALE
2250	2426	SHALE & LIME
2426	3002	LIME & SHALE
3002	3095	LIME & CHERT
3095	3371	LIME
3371	3630	CHALK LIME
3630	3930	LIME & CHALK
3930	4063	CHALK LIME
4063	4438	LIME
4438	4506	LIME & SHALE
4506	5044	LIME
5044	5249	LIME & SHALE
5249	5300	LIME, SHALE & CHERT
5300	5562	LIME & SHALE
5562	5630	SHALE & LIME
5630	5700	LIME & SHALE
5700		TOTAL DEPTH

RECEIVED
STATE CORPORATION COMMISSION
AUG 22 1973
CONSERVATION DIVISION
Wichita, Kansas

THE UNDERSIGNED, LOHMANN-JOHNSON DRILLING CO., INC., HEREBY CERTIFIES THAT
THE ABOVE LOG IS A TRUE AND CORRECT LOG OF THE FORMATIONS ENCOUNTERED IN
DRILLING THE ABOVE WELL AS SHOWN BY THE ~~XXXX~~ DAILY DRILLING REPORTS

LOHMANN-JOHNSON DRILLING CO., INC.

BY Joe Loehr
JOE LOEHR, ASST SECY-TREAS

SUBSCRIBED AND SWORN TO BEFORE
ME THIS 24TH DAY OF FEBRUARY, 1964

Hebert J. Shields
NOTARY PUBLIC
MY COMMISSION EXPIRES
NOVEMBER 5, 1965

RECEIVED
FEB 26 1964

Wichita, Kansas