

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175-20828
-00-01

LEASE NAME M. A. Johnson

WELL NUMBER 1

660 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 35 TWP. 31 SRGE. 34 (X) or (W)

COUNTY Seward

Date Well Completed 5-2-87

Plugging Commenced 6-1-87

Plugging Completed 6-4-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR J. M. Huber Corporation

ADDRESS 7120 I-40 West, Suite 232, Amarillo, TX 79106

PHONE#(806) 353-9837 OPERATORS LICENSE NO. 5703

Character of Well D&A

~~(Oil, Gas, D&A, SWR, Water, Water Supply Well)~~

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dodge City - Mr. Paul Luthe on 6-1-87

Is ACO-1 filed? Yes-attached If not, is well log attached? Previously submitted w/CP-1

Producing Formation None Depth to Top - Bottom - T.D. 5664'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				9-5/8"	1639'	0'
				5-1/2"	5660'	1967'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Sqz'd Oswego perms @ 4836-44' w/1 sx cottonseed hulls followed by 20 sx cmt, displaced cmt w/108 bbls 9.0 mud. Shot off 5-1/2" csg @ 1967', set 50 sx Class "C" plug from 1660-1560', set 25 sx Class "C" plug from 850-750', set 10 sx Class "C" plug from 40' to sfe & capped 9-5/8" csg.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address 620 S. Lincoln, P. O. Box 506, Liberal, KS 67901

STATE OF Texas COUNTY OF Potter, ss.

Frank T. Leder - Manager of Producing Operations (Employee of Operator) or (~~Operator~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Frank T. Leder

(Address) 7120 I-40 West, Suite 232, Amarillo, TX 79106

SUBSCRIBED AND SWORN TO before me this 9th day of June, 1987

Deniese L. Barnett
Notary Public Deniese L. Barnett

My Commission Expires: 6-26-89



1

RECEIVED
STATE CORPORATION COMMISSION

JUN 14 1987

CONSERVATION DIVISION

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
MONTGOMERY, ALABAMA