

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 025-20,932-0005

LEASE NAME Alley

WELL NUMBER 36-1

4950 Ft. from S Section Line

2860 Ft. from E Section Line

SEC. 36 TWP. 31S RGE. 24 (E) or (W)

COUNTY Clark

Date Well Completed 1-31-86

Plugging Commenced 10-10-88

Plugging Completed 10-12-88

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR J. M. Huber Corporation

ADDRESS 7120 I-40 West, Suite 232, Amarillo, Texas 79106

PHONE# (806) 353-9837 OPERATORS LICENSE NO. 5703

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dodge City, Kansas Richard Lacey

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Ste. Genevieve Depth to Top 5654' Bottom 5700' T.D. 5800'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Ste. Genevieve	Gas, Cond & Water	5654'	5700'			
				8-5/8"	1700'	0'
				5-1/2"	5798'	2820'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

- Plug #1 - CIBP @ 5635' topped w/20' cmt. Pmp 60 bbl 9.5# mud down csg to load csg.
 - Plug #2 - 1730-1630' w/100 sx Class H, load csg w/9.5# mud
 - Plug #3 - 850-750' w/50 sx Class H, load csg w/9.5# mud
 - Plug #4 - 40-3' w/10 sx Class H, cut off csg 3' BGL and weld on cap.
- (if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Bruce Well Service License No. 07407

Address P. O. Box 1597, Liberal, Kansas 67901

STATE OF TEXAS COUNTY OF POTTER, ss.

Robert R. Glenn - District Production Manager (Employee of Operator) ~~xxxx Operator~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 7120 I-40 West, Ste 232, Amarillo, TX 79106

SUBSCRIBED AND SWORN TO before me this 1st day of November, 19 88

Notary Public Deniese L. Barnett

My Commission Expires: 6-26-89