

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-025-00058-00-01

LEASE NAME HOUSER

WELL NUMBER #1-6 RE

660 Ft. from S Section Line

4650 Ft. from E Section Line

SEC. 6 TWP. 31 RGE. 25 (E) or (W)

COUNTY CLARK

Date Well Completed 9-28-2001

Plugging Commenced 9-29-2001

Plugging Completed 9-30-2001

RECEIVED

OCT 29 2001

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR KCC WICHITA
CIRRUS PRODUCTION COMPANY

ADDRESS P.O. BOX 5469, ENID, OKLAHOMA 73702

PHONE# 580, 237-0002 OPERATORS LICENSE NO. 32200

Character of Well D&A

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on 9-28-2001 (date)

by STEVE MIDDLETON (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation COUNCIL GROVE Depth to Top 3311 Bottom 3318 T.D. 3380

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
COUNCIL GROVE	WATER	3311	18	4 1/2	3438	2700

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

- 1) SPOTTED 30 SX PLUG @ 3575' ON 9-21-2001 PRIOR TO RUNNING 4 1/2" CASING.
- 2) CIBP @ 3280 + 2 SXS CEMENT 9-29-2001
- 3) 50 SX PLUG @ 2700 150' PLUG BASE=2700 TOP=2550
- 4) 30 SX PLUG @ 710 90' PLUG BASE=710 TOP=620
- 5) 10 SX PLUG @ 40 30' PLUG BASE=40 TOP=10

Name of Plugging Contractor KERR WELL SERVICE License No. 32722

Address P.O. BOX 184, TYRONE, OKLAHOMA 73951-0184

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: CIRRUS PRODUCTION COMPANY

STATE OF OKLAHOMA COUNTY OF GARFIELD, ss.

RAY P. GILL

(Employee of Operator) or (Operator) o

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) R. P. Gill

(Address) P.O. BOX 5469, ENID, OKLAHOMA 73702

SUBSCRIBED AND SWORN TO before me this 22nd day of October, 2001

Allison D. Steidip
Notary Public

My Commission Expires: September 20, 2004

OR