

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-119-20112-0000

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Meade County, Sec. 2 Twp. 31S Rge. (E) 26 (W)

Location as "NE/CNW/SE/SW" or footage from lines 1250'/FSL & 1250'/FWL

Lease Owner Argonaut Exploration, Inc.

Lease Name McBee Well No. 1

Office Address P. O. Box 12099, Amarillo, Texas 79101

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed Sept. 11, 1972

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced Sept. 11, 1972

Plugging completed Sept. 11, 1972

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Edgar Eves of Sublette)



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 5750 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	1513'	8-5/8"	1513'	None
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 1200', 35 sax
Cement; Mud to 40', 1/2 sax Halls, Plug Bridged
and 15 sax Cement to Base of Cellar; 2 sax
in Rat Hole. Job Completed @ 2:30 P.M. by
Dowell on 9/11/72.

RECEIVED
STATE CORPORATION COMMISSION

9-14-72 SEP 14 1972

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Dowell

Address Box 36, Woodward, Oklahoma

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Clarence Michael of Sage Drilling Co. (employee of owner) or former or operator of the above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.


(Signature) Clarence Michael

500 Bitting Building, Wichita, Kansas
(Address)

Subscribed and Sworn to before me this 13th day of September, 1972

Louise K. Whitted
Louise K. Whitted - Notary Public.

Notary Public expires November 26, 1974.



DRILLERS LOG

15-119-20112-0000

McBEE NO. 1

CASING RECORD:	OPERATOR: Argonaut Exploration, Inc.	DESCRIPTION:
8-5/8" @ 1513' w/650 sax cement	CONTRACTOR: Sage Drilling Co., Inc.	1250'/FSL and 1250'/FWL of Sec. 2-31S-26W Meade County, Kansas
TOTAL DEPTH: 5750'	COMMENCED: August 27, 1972	
	COMPLETED: September 11, 1972	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand & Shale	0	400	
Red Bed & Shale	400	1025	
Lime	1025	1035	
Shale & Shells	1035	1150	
Shale	1150	1381	
Anhydrite	1381	1427	
Shale & Anhydrite	1427	1513	
Anhydrite	1513	1577	
Shale	1577	2190	
Shale & Lime	2190	2410	
Shale	2410	2675	
Shale & Lime	2675	2865	
Lime & Shale	2865	2965	
Lime	2965	3330	
Lime & Shale	3330	3565	
Lime	3565	3760	
Lime & Shale	3760	3945	
Lime	3945	4230	
Lime & Shale	4230	4370	
Lime	4370	5750	D&A

RECEIVED
STATE CORPORATION COMMISSION
SEP 14 1972
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

BY Clarence Michael
Clarence Michael

Subscribed and sworn to before me this 13th day of September, 1972.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1974.

