


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Comanche County. Sec. 10 Twp. 31S Rge. 20 (E) W (W)  
Location as "NE/CNW%SW%" or footage from lines. Approx. C NE NE  
Lease Owner D. G. Hamilton  
Lease Name Pounds Well No. 1  
Office Address 1001 Union Center, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) D & A  
Date well completed September 2 19 62  
Application for plugging filed September 2 19 62  
Application for plugging approved September 2 19 62  
Plugging commenced September 2 19 62  
Plugging completed September 2 19 62  
Reason for abandonment of well or producing formation D & A

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. LacKamp, Jr.  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5210 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	521'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with mud to 200'.  
Set plug w/ 1/2 sx hulls &  
20 sx cement. Filled hole to  
20', set plug w/1/2 sx hulls,  
10 sx cement.

**RECEIVED**  
STATE CORPORATION COMMISSION  
**DEC 17 1962**  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Red Tiger Drilling Co.  
Address Box 173 - Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
George A. Angle (employee of owner) or (~~XXXXXX~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George A. Angle  
580 Fourth Nat'l Bank Bldg., Wichita, Kans.  
(Address)

SUBSCRIBED AND SWORN to before me this 5th day of September, 19 62

My commission expires 5-22-66 Jean Hollan Notary Public.



DRILLERS LOG

15-033-19011-0000

Pounds No. 1

CASING RECORD: 8 5/8" @ 521' w/500 sx cement  
 COMPANY: D. G. Hamilton  
 CONTRACTOR: Red Tiger Drilling Co.  
 COMMENCED: August 16, 1962  
 COMPLETED: September 2, 1962

DESCRIPTION: Approx. C NE NE  
 10-31S-20W  
 Comanche Co.,  
 Kansas

ELEVATION:

TOTAL DEPTH: 5210'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	100	
Shale & Shells	100	330	
Hard Lime	330	343	
Shale & Shells	343	500	
Lime & Shale	500	515	
Hard Lime	515	522	
Shale, Lime, Shells & Sand Streaks	522	1125	
Shale with Lime	1125	1880	
Shale and Shells	1880	2080	
Anhydrite	2080	2115	
Shale & Shells	2115	2260	
Shale & Lime	2260	3670	
Lime	3670	3731	
Shale & Lime	3731	3885	
Lime	3885	4200	
Lime with Shale	4200	4290	
Lime	4290	5088	
Lime (Chert)	5088	5120	
Lime	5120	5210	

RECEIVED  
STATE CORPORATION COMMISSION

DEC 17 1962

CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

George A. Angle  
George A. Angle

Subscribed and sworn to before me this 5th day of September, 1962.

Jean Hollan  
Notary Public

My Commission Expires:

5-22-66