


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Clark

County, Sec. 3 Twp. 31 Rge. 21 (E) (W)
Center 1/2 W-SE 1/4

NORTH



Locate well correctly on above
Section Plat

Location as "NE/4NW/4SW/4" or footed from lines
Lease Owner Sen Yeoman
Lease Name Box 163, Ellinwood, Kansas Well No. #1
Office Address _____
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ Yes _____ 19____
Application for plugging filed _____ Yes _____ 19____
Application for plugging approved _____ 19____
Plugging commenced _____ 1-25 _____ 19____
Plugging completed _____ 1-31 _____ 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____
Yes
Mr. Rives

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5237' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		4,425'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured into T.D. 5237'.
Plugging started 1-25-58. Finished 1-31-58.
Plugged off bottom. Set 5 1/2" casing at 4,425'. Had already been
Mixed and circulated 47 sacks mud. Bailed down hole to 375'. Set rock
bridge and dumped 35 sacks cement. Filled hole with mud to 20'. Set
rock bridge and mixed 15 sacks cement for cap on well. Well completed.

Name of Plugging Contractor J.O. Forbes & Co. (Additional description, if necessary, use BACK of this sheet)
Box 221, Great Bend, Kansas
Address _____

STATE OF Kansas COUNTY OF Earton, ss.
J.O. Forbes (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes
Box 221, Great Bend, Kans
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of February, 19 58

My commission expires November 8, 1960
Betty S. Edman
Notary Public.

3-20-58

PLUGGING
FIL. SEC 35 T. 31 R. 21 W
BOOK PAGE 80 LINE 28

CONTRACTOR'S WELL LOG

15-025-00020-0000

Rupp-Ferguson No. 1 Yeoman
C S/2 SE/4, Sec. 3-31-21W,
Clark County, Kansas

Commenced: 2-13-56
Completed: 3-7-56
Contractor: Rupp-Ferguson Oil Co.
Set 104' of 20" w/200 sacks
Set 380' of 13 3/8" w/400 sacks
Set 5231' of 5 1/2" w/100 sacks

Figures Indicate Bottom of Formation

85 sand
127 shale
168 sand, shale, red bed
310 red bed
348 sand & gravel
400 red bed & shale
420 Anhydrite
600 shale & shells
1010 salt & shale
1250 red bed, shale, shells
2405 shale & shells
2545 lime & shale
2720 lime
2800 lime & shale
2830 lime
3085 lime & shale
3160 lime
3830 lime & shale
4095 lime
4325 lime & shale
4427 lime, shale, sand
4493 shale & sand
4534 lime & shale
4816 lime
4864 lime & shale
4890 lime
4945 lime, shale streaks
5000 lime & shale
5130 lime
5162 lime & shale
5201 Core #1
5231 Core #2
5237 Core #3

FILE SEC 35 31 R 21 W
PAGE 80 LINE 28

STATE OF KANSAS, COUNTY OF SEDGWICK SS:

I, L. W. Knox, Landman for Rupp-Ferguson Oil Co., do hereby certify that the above and foregoing is a true and correct copy of the log of the No. 1 Yeoman well.

L. W. Knox
L. W. Knox

Subscribed and sworn to before me this 12th day of March, 1956.

Helen Horine
Notary Public

My Commission Expires June 4, 1959.