


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Pratt County. Sec. 18 Twp. 28 Rge. (E) 12 (W)
Location as "NE/CNW 1/4 SW 1/4" or footage from lines SE/4 SE/4 SW/4
Lease Owner Time Petroleum Company
Lease Name Banbury Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed May 7 19 52
Application for plugging filed May 6 19 52
Application for plugging approved May 7 19 52
Plugging commenced May 7 19 52
Plugging completed May 7 19 52
Reason for abandonment of well or producing formation Dry hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Mr. Rives, Pratt, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4750 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	359	none
				(Circulated top to bottom)		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 4750 feet to 0 feet for each plug set.

Filled hole with heavy mud to 300!
Set a bridging plug @ 300!
Placed 15 sacks of cement on top of plug
Filled hole with heavy mud to 35!
Placed 1/2 sack of hulls on top of plug @ 35!
Placed 10 sacks of cement on top of hulls to top of hole.

RECEIVED
STATE CORPORATION COMMISSION
MAY 13 1952
5-13-52
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Stearns Drilling Company
Address Box 313
Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
O. G. Stearns (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Russell, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 12th day of May 19 52.

[Signature] Notary Public.

My commission expires June 20, 1953

PLUGGING
FILE SEC 18 T 28 R 14
BOOK PAGE 14 LINE 3V

BANBURY #1

Operator: Time Petroleum Company
Contractor: Stearns Drilling Company
Commencement Date: April 7, 1952
Completion Date: May 7, 1952

Location: SE/4 SE/4 SW/4
Section 18-28-12
Pratt County, Kansas

Elevation:

WELL LOG

Cellar	0	5
Shale & Sand	5	260
Red Shale	260	280
Red & Blue Shale	280	287
Shale & Shells	287	415
Red Shale	415	775
Red Bed & Shale	775	985
Shale & Shells	985	1195
Shale & Salt	1195	1368
Shale & Shells	1368	1810
Lime & Shale	1810	3070
Lime	3070	4375
Lime & Shale	4375	4436
Lime	4436	4534
Lime & Sand	4534	4560
Lime	4560	4574
Sand	4574	4578
Lime	4578	4602
Shale	4602	4636
Shale & Lime	4636	4671
Lime	4671	4750
Total Depth	4750	

STATE OF KANSAS) SS
COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

W. Stearns

SUBSCRIBED AND SWORN to before me this 12th day of May, 1952

Harold H. H. H.
Notary Public

My Commission Expires: June 20, 1953

RECEIVED
STATE CORPORATION COMMISSION
MAY 13 1952
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 18-28-12
BOOK PAGE 14 LINE 3