

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-025-20,896-000

LEASE NAME Sawyers

WELL NUMBER 1-27

SPOT LOCATION 1980' FNL &
3135' FWL

SEC. 27 TWP. 31 RGE. 22 ~~XX~~ or (W)

COUNTY Clark

Date Well Completed 5-19-85

Plugging Commenced 5-20-85

Plugging Completed 5-21-85

LEASE OPERATOR Ladd Petroleum Corporation

ADDRESS P. O. Box 2848, Tulsa, Oklahoma 74101

PHONE # (918) 587-6531 OPERATORS LICENSE NO. 6029

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City - Paul Luthi

Is ACO-1 filed? No if not, is well log attached? No - Forwarded separately

Producing formation None Depth to top _____ bottom T.D. 6620'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				16"	40'	None
				8 5/8"	595'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. P&A as follows: 35 sx @ 6000', 50 sx @ 1520', 50 sx @ 620', 10 sx w/ plug @ 40-3', 15 sx rathole & mousehole. All cement 60/40 pozmix w/ 2% gel & 3% CaCl. Mud between plugs - 9.0 ppg w/ 50 second viscosity.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Rains & Williamson Oil Co., Inc. License No. 5146

Address 435 Page Court, Wichita, Kansas

STATE OF OKLAHOMA COUNTY OF TULSA, ss.

K. D. Miller (employee of operator) ~~XXX~~

~~Operator~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) K. D. Miller

(Address) P.O. Box 2848, Tulsa, OK 74101

SUBSCRIBED AND SWORN TO before me this 22 day of May, 19 85

My Commission expires: June 11, 1987

Duty Sue Campbell
Notary Public