

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-025-2815-0000

LEASE NAME Ardrey

WELL NUMBER B#1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

 Ft. from S Section Line

 Ft. from E Section Line

LEASE OPERATOR Pickrell Drilling Co., Inc.

SEC. 2 TWP. 31 RGE. 24 XXXor(W

ADDRESS 110 N. Market, St 205, Wichita, Ks 67202

COUNTY Clark

PHONE# (316) 262-8427 OPERATORS LICENSE NO. 5123

Date Well Completed 8-11-76

Character of Well Oil

Plugging Commenced 5-6-92

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11:00 AM

The plugging proposal was approved on 5-6-92 (date)

by Steve Middleton (KCC District Agent's Name)

Is ACO-1 filed? NA If not, is well log attached? NA

Producing Formation Depth to Top 5451 Bottom 5461 T.D. 5626

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	347	
				4 1/2	5614	2714

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other p were used, state the character of same and depth placed, from feet to feet each: Bottom plug: Sanded to 5400 & bailed 4 sx cement.

Top plug: Pumped 300 lb Hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lb Hulls, 150 sx cement - 60/40 w/6% gel. Had max pressure of 800 lbs & shut in pressure of 200 lbs.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Gasing Pullers, Inc. License No. 4635 CP

Address Box 251, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pickrell Drilling Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.


Gary G. Burke

(Employee of Operator) or (Operator

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Gary G. Burke

(Address) Box 251, Great Bend, Kansas 67530



AND SWORN TO before me this 7 day of May

Anna K. Burke

Notary Public

My Commission Expires: 4-30-96

5-8-92

