


Give All Information Completely  
Make Required Affidavit  
Mail - Deliver Report to:  
Conservation Division  
State Corporation Commission  
1101 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Meade County. Sec. 6 Twp. 31S Rge. 27W (X) (W)  
Location as "NE/CNW%SW%" or footage from lines C SW NE  
Lease Owner Pet-Ex Company  
Lease Name Norman "A" Well No. 1  
Office Address 705 Union Center, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) D & A  
Date well completed September 18 19 61  
Application for plugging filed September 18 19 61  
Application for plugging approved September 18 19 61  
Plugging commenced September 18 19 61  
Plugging completed September 18 19 61  
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J. Lewis Brock  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1455'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

2 sx cement in rathole.  
Filled hole w/heavy mud.  
up to 500'. Set plug.  
1/2 sack hulls. 20 sx cement.  
Filled hole w/mud up to 35'  
set plug. 1/2 sx hulls  
10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

APR 2 1963

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Company  
Address Box 173 -- Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

George A. Angle (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George A. Angle

580 Fourth National Bank Bldg., Wichita,  
Kansas

SUBSCRIBED AND SWORN TO before me this 27th day of September, 1961

Marine Head

Notary Public

My commission expires 11-17-62

15-119-00127-0000

DRILLING LOG

Normal "A" No. 1

CASING RECORD: COMPANY: Dot-Lit Company DESCRIPTION: C 54 SB  
 8 1/8" @ 1400' CONTRACTOR: Red Tiger Drilling Co. 6-310-375  
 w/800 ex cement COMPANY: August 28, 1961 Heade  
 COUNTY, Kansas  
 COMMENCED: September 19, 1961 ELEVATION: 2437 - F  
 2400 RD  
 TOTAL DEPTH: 3002'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Coal sand	0	40	
Shale	40	120	
sand shale	120	170	
Shale, shells, redbed	170	300	
Shale & redbed	300	310	
Lime	310	330	
Shale	330	375	
Shale	375	390	
Sand	390	1000	
Shale redbed sand	1000	1310	
Shale & shells	1310	1432	
Anhydrite	1432	1407	
Gray sandy lime	1407	1480	
Red sand	1480	1978	
Shale & shells	1978	2340	
Shale & lime	2340	2925	
Lime	2925	2970	
Lime & shale	2970	3070	
Lime	3070	3700	
Lime & shale	3700	4350	
Lime	4350	4500	
Lime & shale	4500	4580	
Lime	4580	4740	
Lime & shale	4740	4790	
Lime	4790	4900	
Lime & shale	4900	4970	
Lime	4970	5030	
Lime & shale	5030	5074	
Lime	5074	5101	
Lime & shale	5101	5420	
Lime	5420	6302	

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 APR 2 1963  
 CONSERVATION DIVISION  
 Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

George A. Angle  
 George A. Angle

Subscribed and sworn before me this 27th day of September, 1961.

Notary Seal  
 Notary Public

My Commission Expires:

11-17-63