

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-119-20420-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS. 67202

Meade County, Sec. 19 Twp. 31S Rge. 27W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

C. N/2 N/2
Lease Owner Banks Oil Co.

Lease Name Haskins Well No. 1-19

Office Address Ste. 550, 200 W. Douglas, Wichita

Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole

Date Well completed August 9, 1980

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced August 9, 1980

Plugging completed August 9, 1980

Reason for abandonment of well or producing formation

Dry Hole

If a producing well is abandoned, date of last production

19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen of Pratt, Ks.

Producing formation Depth to top Bottom Total Depth of Well 5440'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	1398'	8-5/8"	1398'	None
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged Hole w/50 sax cement @ 1380',

40 sax cement @ 750', 10 sax cement RECEIVED

@ 40' and 5 sax cement in rat hole. STATE CORPORATION COMMISSION

Job Completed @ 6:30 P.M. 8/9/80.

AUG 27 1980

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton

STATE OF KANSAS COUNTY OF SEDGWICK, ss.


John R. Bartholomew of Sage Drilling Co. ~~(owner or operator)~~
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John R. Bartholomew
222 Sutton Place, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of August, 1980.

Louise K. Whitted
Notary Public.

My commission expires _____



DRILLERS LOG

15-119-20420-0000

HASKINS NO. 1-19

CASING RECORD:	OPERATOR: Banks Oil Co.	DESCRIPTION:
8-5/8" set @ 1398' w/800 sax cement	CONTRACTOR: Sage Drilling Co., Inc.	C N/2 N/2 Sec. 19-31S-27W Meade County, Kansas.
TOTAL DEPTH: 5440'	COMMENCED: July 30, 1980	
	COMPLETED: August 9, 1980	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	90	
Sand & Shale	90	865	
Red Bed & Glorietta Sand	865	1405	
Anhydrite & Sand	1405	1745	
Shale	1745	2447	
Shale & Lime	2447	2452	
Lime & Shale	2452	3388	
Sand & Shale	3388	3635	
Lime & Shale	3635	5326	Ran DST #1
Lime & Shale	5326	5440	Logged Hole, D & A.

I certify that this is a true and correct copy of the log on the above captioned well to the best of my knowledge.

SAGE DRILLING CO., INC.

By John R. Bartholomew
John R. Bartholomew

Subscribed and sworn to before me this 13th day of August, 1980.

Louise K. Whitted
Louise K. Whitted, Notary Public

