

15-119-00219-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Meade County, Sec. 20 Twp. 31S Rge. 27 (E) X (W)

Location as "NE/CNW%SW%" or footage from lines. C SE NW

Lease Owner Helmerich & Payne, Inc.

Lease Name Haskins Well No. 1

Office Address Box 558, Garden City, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 11 Jan 1963 19

Application for plugging filed 11 Jan 1963 19

Application for plugging approved 11 Jan 1963 19

Plugging commenced 11 Jan 1963 19

Plugging completed 11 Jan 1963 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott Liberal, Kansas

Producing formation - Depth to top - Bottom - Total Depth of Well 5645 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		4	1428	8-5/8"	1427	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

5645 to 650 Heavy Rotary Mud  
650 to 550 Plug & 35 sacks pozmix cement  
550 to 45 Heavy Rotary Mud  
45 to 4 Plug & 15 sacks pozmix cement  
4 to 0 Cellar

Plugging Complete 5:00 AM 11 January 1963

JAN 15 1963

CONSERVATION DIV  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Helmerich & Payne, Inc.

Address Utica at 21st, Tulsa, Okla

STATE OF Kansas, COUNTY OF Finney, ss.

T. E. Mort (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. E. Mort

Box 558, Garden City, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 12 day of January, 1963

My commission expires July 1964

Robert N. Boyd Notary Public

Pattie B. Haskins #1  
Helmerich & Payne, Inc.  
Section 20-31S-27W  
Meade County, Kansas

Casing Record:

47 Joints 8-5/8" @ 1427' w/400 sxs.  
P&A

Commenced: 12-21-62  
Completed: 1-11-63

15-119-00219-0000


	<u>FROM</u>	<u>TO</u>
Sand	0	132
Sand & Red Bed	132	900
Salty Anhydrite	900	1460
Sand & Shale	1460	2418
Shale & Salt	2418	2513
Shale & Lime	2513	3863
Lime	3863	4480
Lime & Shale	4480	4574
Lime	4574	5123
Lime & Shale	5123	5169
Lime	5169	5640
<u>Total Depth</u>		<u>5640</u>

RECEIVED  
STATE OF OKLAHOMA DEPT. GEOLOGY  
JAN 24 1963  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF OKLAHOMA )  
  ) SS  
County of Tulsa                 )

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Pattie B. Haskins #1 well, located in Section 20-31S-27W, Meade County, Kansas.

HELMERICH & PAYNE, INC.

  
 \_\_\_\_\_  
 Vice President

Subscribed and sworn to before me a Notary Public this 18th day of January, 1963.

My commission expires: March 30, 1964.

  
 \_\_\_\_\_  
 Notary Public