

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 2/89

**WELL PLUGGING APPLICATION FORM**  
(File One Copy)

API NUMBER 15-025-20,115-0000 Completion Date 8-11-76 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Pickrell Drilling Co., Inc. OPERATOR'S LICENSE NO. 5123 6-92

ADDRESS 110 N. Market, Suite 205 Wichita, Ks. 67202 PHONE # (316) 262-8427

LEASE (FARM) Ardrey "B" WELL NO. 1 WELL LOCATION C-NW-NW COUNTY Clark

SEC. 2 TWP. 31S RGE. 24 (E) or (W) TOTAL DEPTH 5626 PLUG BACK TD 5562

**Check One:**

OIL WELL  GAS WELL  D & A  SWD or INJ WELL  DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8 5/8" SET AT 347 CEMENTED WITH 225 SACKS

CASING SIZE 4 1/2" SET AT 5614 CEMENTED WITH 150 SACKS

PERFORATED AT 5451-5461

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set CIBP above perfs at approx. 5435'. Cut and recover casing

spotting cement plugs as casing is POOH as follows: 50 SX at 1500', 50 SX at 377'. Finish

recover casing. Fill hole from 40' to surface w/cement. NOTE: Contact K.C.C. at (316)225-6760

prior commencing P&A operations. (If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? yes  
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN April 22, 1992

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Ed Mondero PHONE # (913) 798-2430 (D) or (913) 798-2607 (N)

ADDRESS Box 375, Ness City, Ks. 67560

PLUGGING CONTRACTOR Great Bend Casing Pullers LICENSE NO. 4635 9-92

ADDRESS Box 768, Great Bend, Ks. 67530-0768 PHONE # (316) 793-7911

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: [Signature]  
(Operator or Agent)

DATE: 4-20-92

①

Joan Finney  
Governor

Jim Robinson  
Chairman

F. S. Jack Alexander  
Commissioner

Rachel C. Lipman  
Commissioner

Judith McConnell  
Executive Director

Brian Moline  
General Counsel



# Kansas Corporation Commission

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

April 21, 1992

Pickrell Drlg Co Inc  
110 N Market 205  
Wichita KS 67202

Ardrey B 1  
API 15-025-20, 115-0000  
C NW NW  
Sec. 02-31-24W  
Clark County

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). Failure to do so is punishable by an administrative penalty of up to \$1000. If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams  
Production Supervisor

Conservation Division  
William R. Bryson  
Director

200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, Kansas 67202-1286  
Telephone (316) 263-3238

District: #1 304 W. McArtor  
Dodge City, KS 67801  
(316) 225-6760