

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84
RECEIVED
STATE CORPORATION COMMISSION

JAN 16 1990
01-16-90
CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-151-21,862 ⁻⁰⁰⁻⁰⁰ (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Devonian Oil Co. OPERATORS LICENSE NO. 4059 ^{12/90}

ADDRESS 1246 Mass Lawrence, Kansas 66044 PHONE # (918) 841-4508

LEASE (FARM) Rosenbaum WELL NO. 1 WELL LOCATION SW SW NE COUNTY Pratt

SEC. 10 TWP. 28S RGE. 12 (E) or (W) TOTAL DEPTH 4480 PLUG BACK TD 3992

All squeezed below below
3992.

Check One:

OIL WELL XX GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

Conductor pipe 14 3/4"
SURFACE CASING SIZE 10 13/16 SET AT 246 CEMENTED WITH 225 SACKS
8 5/8 852 100 sacks of surefill
CASING SIZE 4 1/2 SET AT 4480 CEMENTED WITH _____ SACKS

PERFORATED AT 3972-76 3964-70

CONDITION OF WELL: GOOD _____ XX POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Top hole plug: Sand back 50' above perfs,
or 3920'. Then dump 4 sx. cement with dump bailer. Top hole plug: 400# hulls,
10 sx. gel., 50 sx. cement, 10 sx. gel, 100# hulls, release plug, 100 sx. cement.
60-40 poz. 6 % gel.

(Cecane Rankin)
(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? _____
(If not, explain)

Gordon Young of Wire Tech in Great Bend, has talked to the state, and he is mailing
me his log on this well under separate cover to you.
DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Jan 15, 1990

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Bruce Wagner of Pratt Well Service, Inc. PHONE # (316) 672-2531

ADDRESS P.O. Box 847 Pratt, Kansas 67124

PLUGGING CONTRACTOR Pratt Well Service, Inc. LICENSE NO. 5893 ^{4/90}

ADDRESS P.O. Box 847 Pratt, Kansas 67124 PHONE # (316) 672-2531

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Judy Perry for Pratt Well Service
(Operator or Agent) Inc.

DATE: 1-12-90

①



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
MARGALEE WRIGHT COMMISSIONER
JUDITH McCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

THIS NOTICE
APR 18 1990
EXPIRES

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

January 18, 1990
NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

Devonian Oil Co.
1246 Massachusetts
Lawrence, KS 66044

Rosenbaum 1
SW SW NE
Sec. 10-28-12W
Pratt County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Handwritten signature of Shari Feist Albrecht.

Shari Feist Albrecht
Director

District: #1 304 W. McArtor
Dodge City, KS 67801
(316) 225-6760